

005N9751 REVISION H October 2025

BWRX-300 General Description




TABLE OF CONTENTS

1.0	INTE	RODUCTION	9
	1.1	Sixty Years in the Making	10
	1.2	Safety Concept and Defense-in-Depth	14
	1.3	Classification of Structures, Systems, and Components	19
	1.4	BWRX-300 Status	23
		1.4.1 Design Progress	23
		1.4.2 Licensing Strategy	24
		1.4.3 License Progress	24
2.0	PLA	NT OVERVIEW	26
	2.1	Unique Design Features	
	2.2	Key Features	29
3.0	NUC	LEAR STEAM SUPPLY SYSTEMS AND COMPONENTS	31
	3.1	Nuclear Boiler System	31
		3.1.1 Reactor Pressure Vessel	
		3.1.2 Main Steam Subsystem	37
		3.1.3 Nuclear Instrumentation	
	3.2	Control Rod Drive System	40
	3.3	Isolation Condenser System	41
	3.4	Containment	
	3.5	Containment Cooling System	45
	3.6	Passive Containment Cooling System	45
	3.7	Boron Injection System	
	3.8	Reactor Water Cleanup System	
	3.9	Shutdown Cooling System	
		Isolation Condenser System Pool Cooling and Cleanup System	
	3.11	Fuel Pool Cooling and Cleanup System	48
4.0	FUE	L AND FUEL CYCLE	
	4.1	Core Configuration	
	4.2	Fuel Assembly Description	49
	4.3	Fuel Handling and Refueling Process	50
5.0	BAL	ANCE OF PLANT	
	5.1	Steam and Power Conversion System	
		5.1.1 Main Steam	53

		5.1.2 Turbine Generator	55
		5.1.3 Main Condenser	56
		5.1.4 Condensate and Feedwater System	56
	5.2	Balance of Plant Auxiliary Systems	57
		5.2.1 Circulating Water System	57
		5.2.2 Chilled Water System	57
6.0	INST	RUMENTATION AND CONTROL SYSTEMS	59
	6.1	Instrumentation and Control Design Architecture	59
	6.2	Main Control Room	61
	6.3	Secondary Control Room	64
7.0	ELE	CTRICAL SYSTEMS	65
8.0	RAD	IOACTIVE WASTE MANAGEMENT SYSTEMS	68
	8.1	Discharges During Normal Operation	68
	8.2	Liquid Waste Management System	68
	8.3	Solid Waste Management System	69
	8.4	Offgas System	69
9.0	PLA	NT LAYOUT AND ARRANGEMENT	70
10.0	SAF	ETY STRATEGY EVALUATION AND ANALYSES	74
	10.1	Introduction	74
	10.2	Overview	77
	10.3	Severe Accident Mitigation	81
11.0	SITE	CONSIDERATIONS AND GRID INTEGRATION	83
	11.1	Site Considerations During Operation	83
	11.2	Grid Integration	83
	11.3	Research, Development, and Testing	85
12.0	TEC	HNOLOGY MATURITY/READINESS	86
13.0	PLA	NT OPERATIONS AND MAINTENANCE	87
14.0	SAF	EGUARDS AND SECURITY	88
	14.1	Safeguards	88
	14.2	Physical Security	89
	14.3	Cyber Security Capabilities	89
	14.4	Resistance to Electromagnetic Pulse and Geomagnetic Disturbances	89
	14.5	Electromagnetic Compatibility	90
15.0	отн	ER PLANT CHARACTERISTICS	91
	15 1	Load Following	01

	15.2	Lower Waste Yields	91
	15.3	Ability to Integrate with Electric and Non-Electric Applications	91
	15.4	Energy Resilience	91
16.0	REA	CTOR END-OF-LIFE	93
	16.1	BWRX-300 Design Life	93
	16.2	BWRX-300 Decommissioning	93
17.0	MAN	UFACTURING AND CONSTRUCTION	94
	17.1	General Plans for Construction	95
	17.2	Improved Construction Approaches	97
		17.2.1 Area-by-Area Modularization of Systems, Structures, and Components	98
	17.3	Approaches to Component Manufacture	100
	17.4	Procurement Plans	101
		17.4.1 Engineering, Procurement, and Construction Procurement	. 101
		17.4.2 GVH Supply Chain	. 102
18.0	ACR	ONYMS, DEFINITIONS, AND SYMBOLS	. 104
	18.1	Acronyms	104
	18.2	Definitions	107
		18.2.1 BWRX-300 Main Parts List Descriptions	. 107
	18.3	Symbols	112
19.0	REF	ERENCES	. 113
20.0	APP	ENDIX A – BWRX-300 PARAMETERS OF INTEREST	. 115
21 0	ΔΡΡ	ENDLY B - BOILING WATER REACTOR EXPERIENCE	110

LIST OF TABLES

Table 1-1: Evolution of the General Electric Boiling Water Reactor	11
Table 1-2: Overview of Defense Line Objectives	16
Table 1-3: Overview of Safety Category Classification	21
Table 1-4: Overview of Safety Classification Methodology	23
Table 2-1: Comparison of Key Features	29
Table 6-1: Safety Classification of Distributed Control and Information Systems	60
Table 10-1: Application of Defense Lines in Safety Analyses	80
Table 20-1: BWRX-300 General Parameters of Interest	115
Table 20-2: BWRX-300 Parameters of Interest	116
Table 21-1: GE Boiling Water Reactors Worldwide	119
Table 21-2: Non-GE Boiling Water Reactors Worldwide	121

LIST OF FIGURES

Figure 1	-1: BWRX-300 Applications	9
Figure 1	-2: Boiling Water Reactor Design Evolution	13
Figure 1	-3: Evolution of Containment Design	14
Figure 1	-4: BWRX-300 Defense-in-Depth Concept	18
Figure 2	-1: BWRX-300 Reactor Building Cutaway	27
Figure 2	-2: BWRX-300 Schematic	28
Figure 3	-1: BWRX-300 Reactor Pressure Vessel and Internals	32
Figure 3	-2: Cutaway View of Reactor Core	35
Figure 3	-3: BWRX-300 Reactor Pressure Vessel Isolation Valve Design	36
Figure 3	-4: Axial Sensor Core Placement	38
Figure 3	-5: Nuclear Instrumentation Ranges	38
Figure 3	-6: Core Map and Instrumentation Layout	39
Figure 3	-7: Fine Motion Control Rod Drive	41
Figure 3	-8: Isolation Condenser System	42
Figure 3	-9: BWRX-300 Dry Containment	44
Figure 3	-10: Passive Containment Cooling System	46
Figure 4	-1: GNF2 Four-bundle Cell and Lattice Array	49
Figure 4	-2: GNF2 Fuel Bundle	50
Figure 4	-3: Fuel Pool Arrangement	51
Figure 4	-4: Refueling Floor (Reactor Building Roof removed)	52
Figure 5	-1: BWRX-300 Reactor Building Main Steam 3D View	54
Figure 5	-2: BWRX-300 Turbine Building Main Steam 3D View	54
Figure 5	-3: Steam Turbine	55
Figure 5	-4: TOPAIR Generator	55
Figure 6	-1: BWRX-300 Distributed Control and Information System Communication Diagram.	60
Figure 6	-2: Main Control Room and Surrounding Areas Layout (Top View)	62
Figure 6	-3: Main Control Room and Surrounding Areas Layout (Side View)	63
Figure 6	-4: Group View Display System Concept (Forward View)	63
Figure 7	-1: Electrical System Architecture	65
Figure 7	-2: Electrical Distribution One-Line Diagram	67
Figure 9	-1: Reactor Building Showing ICS Pools	71
Figure 9	-2: BWRX-300 Site Layout	72
Figure 9	-3: BWRX-300 Site Arrangement	73

Figure	10-1: Configuration of BWRX-300 Plant States	75
Figure	10-2: Safety Strategy Evaluation and Analyses Framework	77
Figure	10-3: Defense Lines and Event Categories per Analysis Type	79
Figure	11-1: BWRX-300 Switchyard Interface	84
Figure	17-1: Existing Technology Use in BWRX-300 Reactor	95
Figure	17-2: BWRX-300 Construction Site	97
Figure	17-3: BWRX-300 Modular Systems, Structures, and Components	99
Figure	17-4: Reactor Building Diaphragm Plate Steel-Plate Composite Installation Sequence	100
Figure	17-5: Reactor Building Structure1	01
Figure	17-6: Reactor Pressure Vessel Installation1	01

DISCLAIMER OF RESPONSIBILITY

This document was prepared by GE Vernova Hitachi Nuclear Energy Americas LLC (GVH) for the purpose of providing general information about its BWRX-300 nuclear power plant. No other use, direct or indirect, of the document or the information it contains is authorized. Neither GVH nor any of the contributors to this document:

- Makes any representation or warranty (express or implied) as to the completeness, accuracy, or usefulness of the information contained in this document or that such use of any information may not infringe privately owned rights; or
- Assumes any responsibility for liability or damage of any kind that may result from any use of such information.

1.0 INTRODUCTION

GE Vernova Hitachi Nuclear Energy's (GVH's) BWRX-300 is a designed-to-cost 300 MWe water-cooled natural circulation Small Modular Reactor (SMR) utilizing simple natural phenomena-driven safety. It is the tenth generation of the Boiling Water Reactor (BWR) and represents the simplest BWR design since General Electric (GE), GVH's predecessor in the nuclear business, began developing nuclear reactors in 1955. The BWRX-300 is an evolution of the U.S. Nuclear Regulatory Commission (USNRC) licensed 1,520 MWe Economic Simplified Boiling Water Reactor (ESBWR) (26A6642AD, ESBWR Design Control Document, Tier 2 – Chapter 1: Introduction and General Description of Plant Sections 1.1-1.11 (2)). It is designed to provide cleaner, flexible energy generation that is cost-competitive with natural gas fired plants. Target applications include base load electricity generation, load following electrical generation generally within a range of 50% to 100% power, hydrogen production, district heating, and other process heat applications, as illustrated in Figure 1-1, BWRX-300 Applications.




Figure 1-1: BWRX-300 Applications

The BWRX-300 design improves the cost of construction, operation, maintenance, staffing, and decommissioning. Costs are reduced while maintaining world class safety by implementing a safety assessment framework structured on the five Defense Lines (DLs) of the International Atomic Energy Agency's (IAEA's) Defense-in-Depth (D-in-D) methodology report (IAEA SSR-2/1, Safety of Nuclear Power Plants: Design (14)). GVH's focus on reducing all aspects of cost was driven by discussions with multiple GVH customers who indicated that new nuclear is only expected to be built in significant quantities if it is cost-competitive with all forms of new energy generation.

Focusing on cost was also borne out as the only path to significant new nuclear generation in a 2018 Electric Power Research Institute report (EPRI 3002011803, *Exploring* the *Role of Advanced Nuclear in Future Energy Markets: Economic Drivers, Barriers, and Impacts in the United States* (6)) and the Massachusetts Institute of Technology (MIT) research (*The Future of Nuclear Energy in a Carbon-Constrained World* (4)).

A study by the International Energy Agency (*Nuclear Power in a Clean Energy System* (18)) and a study commissioned by Energy Northwest (*Pacific Northwest Zero-Emitting Resources Study* (3)) concluded that significant deployments of SMRs are critical to moving to a low carbon economy. Deploying cost-competitive new nuclear significantly reduces the overall cost of a low carbon future.

The goal of GVH's BWRX-300 is to help meet these capital cost targets while significantly improving the plant Levelized Cost of Electricity (LCOE) and levelized cost of heat while maintaining world class safety. By achieving these goals, GVH anticipates deploying a fleet of BWRX-300 reactors to provide a dispatchable cleaner economical source of power for decades to come.

1.1 Sixty Years in the Making

The BWR has its origins in technology developed in the 1950s by Argonne National Laboratory and GE. The first BWR plant built by GE was the 5 MWe Vallecitos plant (1957) located near San Jose, California, United States. The Vallecitos plant confirmed the ability of the BWR concept to produce electricity successfully and safely for a grid. The Vallecitos test facility success led to building the Dresden 1 plant located near Morris, Illinois, United States. Construction of this 180 MWe plant began in 1956 with commercial power production achieved in 1960. The BWR design has subsequently undergone a series of evolutionary changes. Early changes focused on increasing power density and overall power output. Later changes focused on simplification.

While the BWR had its genesis in the United States, it also sparked beginnings in other countries under the Eisenhower administration's "Atoms for Peace" initiative. As examples, the Japan Power Demonstration Reactor (JPDR) BWR introduced nuclear power to Japan, and the KAHL Nuclear Power Plant, which employed an indirect-cycle BWR using steam generators to produce turbine steam, was the first commercial nuclear power plant built in Germany.

The advantage of the indirect-cycle was to avoid radioactive carryover from steam to the turbine, but operations from single (direct) and dual-cycle plants demonstrated that the process of boiling itself provided a natural separation process that tended to leave activated radioactive impurities in the vessel water, and this process was further enhanced with the introduction of in-vessel steam separation and a reactor water cleanup system.

And so, during the 1950s and into the 1960s, when the BWR was in its infancy, it grew by exploring different options and design configurations, feeding back operating experience gained. As a result, standardization did not exist to the extent that it would for future product lines of the Generation II reactors. While the various Generation I BWR configurations successfully operated for many years, operating experience along with improvements in manufacturing capabilities eventually drove toward forced circulation, internal vessel steam separation, and direct-cycle BWRs as a standard configuration.

The ever-evolving BWR design has been simplified in two key areas – the reactor systems and the containment design. Table 1-1, *Evolution of the GE Boiling Water Reactor* chronicles the development of the BWR.

Table 1-1: Evolution of the General Electric Boiling Water Reactor

Product Line	First Commercial Operation Date	Representative Plant/Characteristics	
BWR/1	1960	Dresden1 Initial commercial-size BWR	
BWR/2	1969	Oyster Creek Turnkey project purchased solely on economics. Large direct cycle External recirculation pumps	
BWR/3	1971	Dresden 2 First jet pump application Improved Emergency Core Cooling System (ECCS) Core spray and flood capability	
BWR/4	1972	Vermont Yankee Increased power density (20%)	
BWR/5	1978	Tokai 2 Improved ECCS Valve flow control for recirculation system	
BWR/6	1981	Kuosheng 1 Compact control room Solid-state nuclear system protection system Advanced containment design	
ABWR	1996	Kashiwazaki-Kariwa 6 Reactor internal pumps Fine Motion Control Rod Drives (FMCRDs) Advanced control room, digital and fiber optic technology Improved ECCS: high/low-pressure flooders	
SBWR		Natural circulation Passive ECCS Passive containment cooling	
ESBWR		Natural circulation Passive ECCS Passive containment cooling	
BWRX-300		Loss-of-Coolant Accident (LOCA) mitigation through integral isolation valves Natural circulation Passive heat removal systems Reactor Building (RB) built from steel-concrete composite modules with diaphragm plates	

Dresden 1 was based on a dual steam cycle rather than the direct steam cycle that characterizes later generation BWRs. Steam was generated in the reactor and flowed to an elevated steam drum and secondary steam generator before reaching the turbine. The first step in BWR simplification was elimination of the external steam drum. This was achieved by two technical innovations, the internal steam separator, and the steam dryer at Gundremmingen (KRB-A, 1967). The simplification of the design using technical innovations has been repeated with each new iteration.

The first large direct cycle BWRs (e.g., Oyster Creek) appeared in the late-1960s and were characterized by elimination of steam generators and the use of five external recirculation loops. Later plants were simplified by the introduction of internal jet pumps. These pumps boosted recirculation flow so that only two external recirculation loops were needed. Jet pumps first appeared in the Dresden-2 BWR/3 plant. BWR/4, BWR/5, and BWR/6 designs continued the path to simplification with the changes shown in Table 1-1, above.

The use of reactor internal pumps in the Advanced Boiling Water Reactor (ABWR) design represents another simplification. By using pumps attached directly to the vessel, jet pumps and external recirculation systems (with associated pumps, valves, piping, and snubbers) were eliminated. The ESBWR and its smaller predecessor the Simplified Boiling Water Reactor (SBWR) are a result of the logical simplification of using a taller vessel and shorter core to achieve natural recirculation flow without the use of any pumps.

BWRX-300 continues the cost-saving advances of the SBWR and ESBWR with a tall vessel design to achieve natural circulation but without the need for a shorter core. This allows the BWRX-300 to use the same fuel bundle designs in use in the operating BWR fleet. Challenges to the integrity of the system are reduced by the large water inventory above the core in the Reactor Pressure Vessel (RPV).

Figure 1-2, *Boiling Water Reactor Design Evolution* illustrates the evolution of the reactor system design. Most BWRs deployed to date have used forced circulation including the BWR/1s through BWR/6s and the ABWR. Natural circulation plants have a separate lineage from the Vallecitos plant through Humboldt Bay and Dodewaard to the SBWR, ESBWR, and BWRX-300.




Figure 1-2: Boiling Water Reactor Design Evolution

The first BWR containments were spherical "dry" structures. Dry spherical and cylindrical containments are still used today in Pressurized Water Reactor designs. Future BWRs, including the ABWR and ESBWR, utilized a pressure suppression containment design that allowed for a smaller size and the ability to accommodate rapid depressurization of the RPV. The BWRX-300 has gone back to the dry containment configuration because Isolation Condensers (ICs) manage RPV pressure and Safety Relief Valves have been eliminated as described in Section 2.0 of this document.

The Mark I containment used for BWR/3, and most BWR/4 plants was the first of the pressure suppression containment designs. The Mark I design has a characteristic "inverted" light bulb configuration for the steel drywell surrounded by a steel torus housing the large pool of water for pressure suppression. The conical Mark II design used for some late BWR/4, and BWR/5 plants is a less-complicated arrangement allowing simplified construction. The Mark III containment design in BWR/6 plants represented a further improvement in simplicity; the containment structure is a right-circular cylinder that is easy to construct while providing access to equipment and space for maintenance activities.

The ABWR containment is smaller than the Mark III containment because the elimination of the recirculation loops translates into a more compact containment and RB. The ESBWR containment is similar in design to the ABWR but is larger to accommodate the passive ECCS systems.

The BWRX-300 containment is small and simple and is achieved with surface-mounted integral RPV isolation valves to rapidly isolate the flow from a downstream pipe break to reduce pressure and temperature buildup in the containment. An Isolation Condenser System (ICS) removes energy from the RPV rather than directing that energy into a suppression pool. Figure 1-3, *Evolution of Containment Design*, illustrates the history of BWR containment (outlined in blue) and RB development.




Figure 1-3: Evolution of Containment Design

1.2 Safety Concept and Defense-in-Depth

BWRX-300's safety strategy implements the safety requirements set forth in IAEA SSR-2/1, Rev. 1, *Safety of Nuclear Power Plants: Design.* The safety requirements are implemented through Defense-in-Depth (D-in-D) concepts, evaluations, analyses, and assessments used in the design process.

The Safety Strategy considers the five plant states described below:

- 1. **Normal Operation** includes the operational states that are expected to occur frequently or regularly during plant operation, including the following Normal Plant Operational Modes that cause the extreme values of basic plant parameters (e.g., system pressures, system flow rates, radiation levels, or component stresses):
 - Power Operation
 - Startup
 - Hot Shutdown
 - Stable Shutdown
 - Cold Shutdown
 - Refueling
 - Maintenance
 - Maneuvering of the plant

This limiting set of normal operations determines the control requirements and administrative restrictions necessary to help ensure that protective actions are not required during normal operation.

2. **Anticipated Operational Occurrences** are deviations from normal operation that are expected to occur at least once during the operating lifetime of the reactor facility but that, with the appropriate design measures, do not cause any significant damage to safety class components, or lead to accident conditions. The Anticipated Operational Occurrence (AOO) plant state includes all Postulated Initiating Event (PIEs) with frequencies of occurrence greater than 10⁻² per year.

Therefore, this plant state is characterized as a condition initiated by an active incident and expected to occur at least once during the lifetime of the plant. These occurrences have the potential to challenge the reactor safety, but, at worst, result in a reactor trip with the plant capable of being returned to normal operation.

- 3. **Design Basis Accidents** are accident conditions for which a reactor facility is designed according to established design criteria, and for which damage to the fuel and the release of radioactive material are kept within regulated limits. Design Basis Accidents (DBAs) include all PIEs with frequencies of occurrence greater than 10⁻⁵ per year but lower than 10⁻² per year and any events that are used as a design basis for DL3, regardless of whether the estimated frequencies are lower than 10⁻⁵ per year.
 - Therefore, this plant state is typically characterized by passive incidents that occur infrequently or are not expected to occur during the lifetime of the plant.
- 4. **Internal hazards** include events such as fires, explosions, turbine missile impacts, and floods of internal origin, which could affect the safety of the reactor and result in damage to Structures, Systems, and Components (SSCs) important to safety.

External events include events that might prevail in the vicinity of the site and challenge the Fundamental Safety Functions (FSFs) include:

- Natural external hazards such as extreme weather conditions, earthquakes, and external flooding.
- Man-made hazards such as aircraft crashes, hazards arising from transportation, and industrial activities (fire, explosion, missiles, release of toxic gases).

Internal hazards and external events determine requirements for SSCs important to safety, including design, redundancy, protection, and separation.

5. Design Extension Conditions are postulated accident conditions that are less frequent than DBAs. Design Extension Conditions (DECs) are a subset of BDBAs, and are therefore, not part of the design basis. DECs are considered in the design process of the facility in accordance with best-estimate methodology DECs can occur without core damage or with core damage where releases of radioactive material are reasonably contained and kept within acceptable limits.

BDBAs other than DECs are accidents for which confinement of radioactive materials cannot be reasonably achieved. These are referred to as severe accidents and involve a catastrophic incident, core damage, and fission product release. These accidents scenarios are considered for practical elimination. A severe accident is generally considered to begin with the onset of core damage.

Representative DECs with core damage are postulated to provide inputs for the design of the containment and of the safety features ensuring containment functionality. Analyses of DECs determine the requirements for this plant state, the performance of protective SSCs, administrative restrictions, and quantify the plant safety margin.

The safety strategy incorporates international expectations for the design of new nuclear power plants that include rules for identification of specific plant states and relevant systems to cope with the plant states. It provides guidance for applying D-in-D concepts, including design extension conditions and practically eliminated conditions, and addresses radiological acceptance criteria and implementation strategies.

The approach aims to reduce doses to people and the probability of an early or large release of radioactivity outside the plant or site boundary because of postulated and potentially credible accident scenarios. The overall general safety objective is to protect people and the environment from harmful effects of ionizing radiation, consistent with IAEA SF-1, *Fundamental Safety Principles*, (10).

One part of achieving the safety objective is to identify and protect FSFs that protect the public and the local community utilizing So Far As Is Reasonably Practicable (SFAIRP) principles to improve the safety of the plant, the environment, and the local community. Successful performance of these functions prevents events from escalating from one DL to the next and thereby prevents or mitigates a radiological release. In other words, if the FSFs are performed successfully for a given pant scenario, then the corresponding physical barriers remain effective. The three FSFs for the BWRX-300 are:

- Control of reactivity.
- Removal of heat from the fuel (in the reactor, during fuel storage and handling, and including long-term heat removal).
- Confinement of radioactive material, shielding against radiation and control of planned radioactive releases, as well as limitation of accidental radioactive releases.

A combination of active, passive, and inherent safety features and functions, as well as design and operational practices, which reduce challenges to the physical barriers, maintain the integrity of the barriers when challenged and, in case a barrier is breached, help ensure the integrity of the remaining barriers. These features, functions, and practices are organized into the five Defense Lines defined in Table 1-2, *Overview of Defense Line Objectives*, and illustrated in Figure 1-4, *BWRX-300 Defense-in-Depth Concept*, consistent with the IAEA approach.

Table 1-2: Overview of Defense Line Objectives

Defense Line	Objective				
DL1	Reduce potential for incidences and initiating events to occur in the first place and reduce potential for incidences to occur in subsequent lines of defense.				
DL2 Actively control key plant parameters associated with FSFs and detect and mitig					
DL3	Detect and mitigate DBA PIEs and event sequences comprising AOO PIEs and incidence of DL2 functions.				
DL4a	Detect and mitigate DECs, including event sequences associated with some DBA PIEs and incident of DL3 functions.				
DL4b	Detect and mitigate DECs to prevent core damage or mitigate the consequences of core damage events (severe accidents).				

Table 1-2: Overview of Defense Line Objectives

Defense Line	Objective
DL5	Employ emergency preparedness measures to protect the public from consequences of significant releases of radioactive materials.

The following high-level principal safety objectives are considered in the Safety Strategy:

- Improve protection to provide the highest level of safety that can reasonably be achieved.
- Produce a design with an appropriate degree of accident prevention and consequence mitigation features.
- Provide a hazard evaluation process to identify hazards with potential to challenge a FSF.
- Systematically identify and categorize plant level safety functions and flow down requirements to Systems, Structures and Components (SSC)s delivering those plant level safety functions.
- Incorporate probabilistic risk assessment insights to select among design options, strengthen the design against previously known vulnerabilities, characterize the design, and evaluate the balance in the design between severe accident prevention and mitigation, leading to a well-balanced and cost-effective improvement in safety.
- Appropriately include or improve upon features in predecessor designs that reduce risks associated with postulated accident events, such as a diverse scram system with both hydraulic and electric run-in capabilities on the control rods.
- Establish a design approach where active asset protection systems and blocking systems serve as the primary means to mitigate anticipated operational occurrences (i.e., DL2).
- Establish a passive approach with simple systems that use driving forces of buoyancy, gravity, core heat generation, and stored energy sources to mitigate DBAs (i.e., DL3).
- Associated with the passive design approach, deterministic design basis safety analyses
 are to rely solely on the passive safety systems and fail-safe repositioning of components
 to demonstrate compliance with the acceptance criteria for various design basis events.
- Provide a structured and deliberate approach to help meet international expectations that
 events and sequences outside of the traditional design basis be analyzed deterministically
 and probabilistically to show that they are not to escalate into a severe accident.
- Establish the appropriate quality and diversity in digital instrumentation and control Systems to defend against Common Cause Failures (CCF).




Figure 1-4: BWRX-300 Defense-in-Depth Concept

The BWRX-300 is designed for international deployment and is, therefore, utilizing standards published by the IAEA, in lieu of specific regulatory requirements for any given country. The IAEA Safety Standards represent an international consensus on what measures constitute a high level of protection and safety and utilize D-in-D as "the primary means of preventing accidents in a Nuclear Power Plant (NPP) and mitigating the consequences of accidents if they do occur". The BWRX-300 design is in alignment with this international framework irrespective of licensing requirements in any specific region. Region-specific adaptations can be made for specific design or analysis elements (e.g., region-specific acceptance criteria for dose releases), but the role of that element should not change.

The concept of D-in-D involves the provision of multiple layers of defense against some undesirable outcome rather than a single, strong defensive layer. In the case of an NPP, the undesirable outcome is the exposure of workers or the public to radioactivity that exceeds a safe level.

To understand the principle of D-in-D, it is important to differentiate two types of defensive layering:

- Physical barriers in place to prevent release of radioactivity: the fuel cladding, Reactor Coolant Pressure Boundary (RCPB), and containment. The integrity of one or more physical barriers is to be maintained to prevent unacceptable releases.
- Features, functions, and practices used to reduce challenges to the physical barriers, to maintain the integrity of the barriers and, in case a barrier is breached, to help ensure the integrity of the remaining barriers.

The physical barriers themselves represent multiple layers of defense against radioactive releases. In the BWRX-300 D-in-D concept, shown in Figure 1-4, the physical barriers are not themselves referred to as "defense lines." That term is reserved for the layers of defense comprising features, functions, and practices that protect the integrity of the barriers. In fact, the D-in-D concept is largely focused on identifying and organizing features, functions, and activities into DL without explicit acknowledgment of the physical barriers. It should, however, be understood that the fundamental purpose of the layered DLs is to help ensure the integrity of the layered physical barriers.

1.3 Classification of Structures, Systems, and Components

The BWRX-300 safety classification process follows the guidance provided in CNSC REGDOC-2.5.2, *Design of Reactor Facilities: Nuclear Power Plants* (21). This process starts with identifying functions that impact nuclear safety, extends to assigning a safety category to those functions based on their importance to safety, and then assigning a Safety Class (SC) to the SSCs that perform those functions, thereby establishing the importance of the SSCs. This importance is then reflected in the application of requirements to the SSCs that perform the safety functions.

The design basis deterministic safety analyses are performed and updated iteratively with design activities to establish the plant-specific functions responsible for maintaining the I FSFs during event sequences.

Assignment of a function designed to mitigate one or more PIEs to a DL reflects its relative importance to safety and its role in maintaining the FSFs under off-normal conditions. As such, the safety categorization of mitigating functions is based on the DLs they support. The FSFs for the BWRX-300 are:

- Control of reactivity
- Removal of heat from the fuel (in the reactor, during fuel storage and handling, and including long-term heat removal)
- Confine radioactive materials

Plant-level requirements are created for each DL function. These requirements are translated into system-specific functional requirements to implement the credited DL functions, consistent with the plant performance modeled in the safety analyses. These requirements are then allocated to the applicable system design description where the components that carry out the system DL functions are identified.

Primary functions are those that directly perform the FSFs in support of DL2, DL3, DL4a or DL4b. Some examples are given in Table 1-3, *Overview of Safety Category Classification*. Safety Categories are applied to the primary functions as follows:

Safety Category 1 is assigned to DL3 primary and integral functions. DL3 functions assure
the integrity of the barriers to release, place, and maintain the plant in a safe state, and
provide independence and diversity for all DL2 and DL4a functions caused by a single
incident (and many CCFs). Accordingly, DL3 primary functions are the most important
from a safety standpoint.

Safety Category 2 is assigned to DL4a primary and integral functions. Both DL2 and DL4a provide a redundant means to address PIEs (generally independent of DL3 functions) and are therefore important from a safety standpoint, although less important than DL3 functions. DL4a functions are a backup to DL3 functions, in the unlikely event a DL3 functions fails, and therefore have a higher consequence of incident than DL2 functions and are more important from a safety standpoint than DL2 functions.

- Safety Category 3 is assigned to DL2 and DL4b primary and integral functions as they are
 relatively the least important. DL4b functions address severe accidents, which are
 extremely unlikely because incident of both DL3 and DL2 or DL4a functions would have
 to occur. Accordingly, DL4b functions are considered relatively the least important defense
 line functions, despite the high consequence of incident.
- Non-Safety Category is assigned to all other functions.

In addition to primary functions, make-ready support functions, delayed functions, normal functions, and Post-Accident Monitoring (PAM) functions are also assigned safety categories. Safety Categories are applied to these functions as described below:

Make-ready support functions are continuously available online functions that maintain the primary function, or a component required to perform the primary function, in a state of readiness but are not required to be performed at the time the primary function is performed. Make-ready functions have monitoring, such that plant operators are alerted if the make-ready support function were lost, or the readiness of the primary function or component were compromised. For example, maintaining the temperature of a pool of cooling water within acceptable limits, with monitoring by pool temperature indication is an example of a make-ready support function. Accordingly, make-ready functions are not required to be assigned the same safety category as the primary function. However, make-ready functions are important and are therefore assigned to safety categories as follows:

- Make-ready functions that support DL3 or DL4a functions are assigned to Safety Category 3
- All other make-ready functions are assigned to Safety Category N

Delayed functions are primary or integral support functions that are not required to be performed until sometime after the initiating event. Because there would be ample time during the event to help ensure these functions are available, delayed functions are not required to be assigned the same safety category as functions required immediately after the initiating event. If the function is not needed until after 72 hours into the event (but before seven days), it is classified as Safety Category 2 (instead of Safety Category 1), and if the SSC is not needed until after seven days into the event, it is classified as Safety Category 3 (instead of Safety Category 1 or Safety Category 2). Delayed functions are not subject to defense line function "requirements," such as independence and diversity.

Normal functions that perform an FSF during normal plant operation or that maintain key reactor parameters (e.g., reactor pressure and temperature) within normal ranges, and their integral support functions, are assigned to Safety Category 3. Make-ready functions for normal functions are assigned to Safety Category N. If incident of a normal function would likely result in an initiating event that could challenge an FSF, the function should be assigned to Safety Category 3.

Functions that support monitoring and display of PAM variables are assigned the following safety categories:

 Safety Category 1 is assigned to functions that support monitoring and display of PAM Type A variables unless a further evaluation is performed to justify a lower safety category.

• Safety Category 3 is assigned to functions that support monitoring and display of PAM Types B - F variables.

Table 1-3: Overview of Safety Category Classification

Safety Category	DL3 Functions	DL4a Functions	DL2/4b Functions	Normal Functions	Post-Accident Monitoring Functions
1	Primary and Integral support functions initiated during the first 72 hours of an event				Functions that support monitoring and display of PAM Type A variables, unless further evaluation is performed to justify a lower safety category
2	Primary and integral support functions required after 72 hours but before the end of seventh day after an event	Primary and integral support functions initiated during the first 7 days of an event			
3	Primary and integral support functions initiated after 7 days after an event Make-ready support functions	Primary and integral support functions initiated after 7 days Make-ready support functions	All primary and integral support functions	Normal functions that perform an FSF Normal functions that maintain key reactor parameters (e.g., pressure, temperature) within normal ranges Integral support functions	Functions that support monitoring and display of PAM Type B, C, D, E, and F variables
N			Make-ready support functions	Make-ready support functions	

Safety Class is assigned to components based on the safety category of the functions they perform as follows:

Safety Class 1 (SC1) is assigned to SSC that perform a Safety Category 1 function.

Safety Class 2 (SC2) is assigned to SSC that perform a Safety Category 2 function.

Safety Class 3 (SC3) is assigned to SSC that perform a Safety Category 3 function.

Non-Safety Class (SCN) is assigned to all other SSC.

Just as with functions, a time-dependency is introduced for components that perform or support DL3 and DL4a functions. Specifically, if the component is not needed until after 72 hours into the event (but before seven days), it is classified as SC2 (instead of SC1), and if the component is not needed until after seven days into the event, it is classified as SC3 (instead of SC1 or SC2) because there would be ample time during the event to help ensure those components are available.

The following classifications are made for components that perform FSFs but may not be explicitly defined as part of a DL function:

1. Components that are part of design provisions that perform a FSF, whose incident is considered "practically eliminated," are assigned to SC1. An example is the Reactor Pressure Vessel (RPV).

Components that make up the fission product barriers, i.e., fuel cladding, RCPB, and containment, are assigned to SC1.

- a. Based on USNRC 10 CFR 50.2 (23), "RCPB includes all those pressure-containing components of boiling and pressurized water-cooled nuclear power reactors, such as pressure vessels, piping, pumps, and valves, which are either part of the reactor coolant system, or connected to the reactor coolant system, up to and including any and all of the following:
 - The outermost Containment Isolation Valve (CIV) in system piping which penetrates primary reactor containment.
 - The second of two valves normally closed during normal reactor operation in system piping which does not penetrate primary reactor containment.
 - The reactor coolant system safety and relief valves.

For nuclear power reactors of the direct cycle boiling water type, the reactor coolant system extends to and includes the outermost CIV in the main steam and feedwater piping."

Table 1-4: Overview of Safety Classification Methodology

Safety Class	Safety Category 1 Functions	Safety Category 2 Functions	Safety Category 3 Functions	Safety Category N Functions	Other
1	SSCs required within first 72 hours of event				Components that are part of design provisions that perform an FSF, whose incident is considered "practically eliminated" Components that make up the fission product barriers Components that are part of the reactor coolant pressure boundary
2	SSCs required after 72 hours but before the end of the seventh day	SSCs required within first 7 days of event			
3	SSCs required after 7 days	SSCs required after 7 days	All components		
N				All components	

Structures (excluding fuel handling equipment) are assigned a safety classification based on the highest safety classification of the components they house or support, excluding components whose incident, due to loss of functionality of the structure, would result in fail-safe performance of the component's safety category function(s).

1.4 BWRX-300 Status

1.4.1 Design Progress

GVH is currently finalizing the BWRX-300 standard design. The design was used as the basis of the issuance of the License to Construct for the lead unit, Ontario Power Generation's Darlington New Nuclear Project Unit 1, the Construction Permit Application for Tennessee Valley Authority's Clinch River Nuclear Unit 1, interactions with Poland's nuclear regulator and the first two steps of the United Kingdom regulators" Generic Design Assessment.

1.4.2 Licensing Strategy

GVH is developing a BWRX-300 standard plant design that can be licensed in the U.S., Canada, and Europe. Therefore, the BWRX-300 standard plant design is based, wherever possible, on meeting the requirements and guidance of the IAEA Safety Standards consisting of the three basic sets of IAEA publications: the Safety Fundamentals, the Safety Requirements, and the Safety Guides. While the first one of these establishes the fundamental safety objective and principles of protection and safety, the second set out the requirements that is to be met to help ensure the protection of people and the environment, both now and in the future. The Safety Guides provide recommendations and guidance on how to comply with the requirements.

BWRX-300 standard plant design incorporates D-in-D in the design of the plant in conformance with INSAG-10, *Defense in Depth in Nuclear Safety* (16). The BWRX-300 Safety Strategy is based on the IAEA Safety Requirement SSR-2/1 (14). Some of the IAEA Safety Guides that are a part of the BWRX-300 Safety Strategy include the following:

- IAEA SSG-2, Deterministic Safety Analysis for Nuclear Power Plants (10)
- IAEA SSG-30, Safety Classification of Structures, Systems and Components in Nuclear Power Plants (12)
- IAEA SSG-53, Design of the Reactor Containment and Associated Systems for Nuclear Power Plants (13)

Although every attempt is made to conform to the IAEA Safety Standards, there are cases where alternate approaches or exceptions are incorporated into the BWRX-300 standard plant design. Some of these are based on meeting more limiting country-specific regulations or guidance, while others are based on the specifics of the BWRX-300 technology where requirements or guidance are either not applicable or are not necessary to help meet the applicable safety goals. In addition, the BWRX-300 utilizes a design-to-cost approach that evaluates design alternatives that achieve the required safety goals to determine the most cost-effective design, construction, commissioning, operations, maintenance, inspection, testing, and decommissioning approaches for the BWRX-300 standard plant design.

1.4.3 License Progress

The BWRX-300 has undergone a preapplication review with the United Kingdom (U.K.) Office for Nuclear Regulation and is in the process of preapplication reviews by the USNRC and the Canadian Nuclear Safety Commission (CNSC). The purpose of these licensing preapplication activities is to present a standard design approach that helps meet regulatory requirements and guidance while increasing regulatory certainty. The review activities introduce the innovative design features and analysis methods used for the BWRX-300 prior to actual submittal of complete license applications.

In Canada, the Vendor Design Review process confirmed that there are no fundamental barriers to licensing based on Canadian regulations and regulatory guidance. The Vendor Design Review process was completed in March 2023. There have been no significant issues representing barriers to licensing identified by CNSC to date. A License to Construct for a BWRX-300 project was approved by CNSC in April 2025. The Pre-Operational Safety Analysis Report and License to Operate (LTO) application are currently under development.

In the U.S., a decision was made during the licensing preapplication process to submit Licensing Topical Reports (LTRs) for design features and analysis methods considered to have lower regulatory certainty. GVH has submitted a series of LTRs to increase the risk certainty of the licensing process for the BWRX-300 in the U.S. LTRs are used to obtain regulatory approval of

key enabling technologies prior to performing detailed design activities. Additional LTRs are to be submitted to support other aspects of the BWRX-300 design. Preapplication LTRs may also be prepared to support U.S. operating utility partner plans currently in development. The intent of further LTRs is to streamline the review process for plant-specific licensing applications. A Construction Permit submittal was filed with the USNRC in May 20252025 and accepted for review with an expected CP issuance timeline of December 2026.

In the U.K., the BWRX-300 is currently being assessed as part of the Generic Design Assessment (GDA) completed by the ONR and EA. As part of the 2-step GDA, the BWRX-300 core safety, security and environmental protection cases are assessed in order to confirm there are no 'show stopping' shortfalls, paving the way for future site licensing and permitting activities in the UK. The regulators assessment is on track for completion in December 2025.

GVH is supporting potential deployment of the BWRX-300 in Poland with partners. The government of Poland approved six locations for the construction of 24 BWRX-300 SMRs, and a generic Preliminary Safety Analysis Report is under development. GVH, along with our partners, is in preapplication discussions with the National Atomic Energy Agency of Poland (PAA). PAA has also communicated to GVH that discussions regarding development of a collaborative agreement with both the USNRC and CNSC are in progress.

In support of potential deployment of the BWRX-300 in the Czech Republic, GVH, along with our partners, is in preapplication discussions with the State Office for Nuclear Safety (SÚJB) and the Radioactive Waste Repository Authority (SURAO). SÚJB and SURAO have also communicated to GVH that discussions regarding development of a collaborative agreement with both the USNRC and CNSC are in progress. Although there are existing commercial NPPs in the Czech Republic, the existing nuclear regulations are not as mature as in Canada and the U.S. Therefore, GVH and our partners have been in discussions with the SÚJB and SURAO for consideration of using country-of-origin licensing from either or both Canada and the U.S. to supplement the country's existing nuclear regulations, including acceptance of use of IAEA Safety Standards.

GVH is supporting potential deployment of the BWRX-300 in Finland and/or Sweden with partners. A pre-engineering phase for potential new build has commenced for certain assessments being carried out to take the first steps in the nuclear licensing process for potential technologies. One assessment includes a review of Finland Radiation and Nuclear Safety Authority (STUK) and Swedish Radiation Safety Authority (SSM) regulations to identify and mitigate licensing risks during future project phases. Pre-licensing dialogue continues and is aimed to reduce licensing risk at later stages of the project.

2.0 PLANT OVERVIEW

The BWRX-300 builds on the success and lessons learned from over 60 years of BWR operating history. The important characteristics of the BWRX-300 include:

- 10th generation BWR
- Evolved from USNRC licensed ESBWR
- Design-to-cost approach
- Significant capital cost reduction per MW
- World class safety
- Capable of load following
- Suitable for electricity generation and industrial applications, including hydrogen production
- Constructability integrated into design
- · Reduced on-site staff and security
- Intended to be licensable internationally

The BWRX-300 improves innovation with technology readiness. It relies on fuel that is already licensed, currently in use globally, and used by the majority of the BWR fleet. The design improves material and manufacturing techniques while incorporating breakthrough passive and simple concepts. The result is a cost-effective advanced reactor design with world-class safety and economic performance that can be licensed and constructed in the near-term. It offers low risk in comparison to historical large Light Water Reactor (LWR) projects in the U.S., Europe, and Asia, and it promises to be highly competitive in the worldwide energy industry.

The key simplifications of the BWRX-300 are the use of integral RPV isolation valves that mitigate the impacts of LOCAs, and large capacity ICs that provide over pressure protection without the need for safety relieve valves. The ICs also act as the ECCS, utilize natural circulation, and require no Alternating Current (AC) power to perform their functions.

A cutaway of the BWRX-300 RB is shown in Figure 2-1, *BWRX-300 Reactor Building Cutaway*. An artist's rendering of the major systems and how those systems interconnect is shown in Figure 2-2, *BWRX-300 Schematic*.




Figure 2-1: BWRX-300 Reactor Building Cutaway




Figure 2-2: BWRX-300 Schematic

2.1 Unique Design Features

Though mostly traditional in BWR design, the BWRX-300 includes several design features that simplify the design and support reduced costs. These features include:

1. Integral RPV isolation valves: The BWRX-300 RPV is equipped with isolation valves that are integral to the RPV that rapidly isolate a ruptured pipe to help mitigate the effects of an LOCA. All large fluid pipes with RPV penetrations are equipped with double isolation valves that are integral to the RPV.

No Safety Relief Valves (SRVs): SRVs have been eliminated from the BWRX-300 design. The large capacity ICS in conjunction with the large steam volume in the RPV provides overpressure protection in accordance with American Society of Mechanical Engineers (ASME) Boiler and Pressure Vessel Code (BPVC), Section III, Class 1 equipment. Historically, BWR SRVs have been the most likely cause of an LOCA but have been eliminated from the BWRX-300 design.

Dry containment: The BWRX-300 has a dry containment. This has been proven to effectively contain the releases of steam, water, and fission products after a LOCA.

Design-to-cost: The BWRX-300 has been designed with cost and constructability in mind from the start, beginning with a simplified system layout that requires fewer safety systems and safety-related pools of water. This concept has also been adapted to fit with commercial building standards and cost and labor-efficient construction techniques for underground structures. The design has been improved for constructability.

Use of commercial off-the-shelf equipment: Due to its smaller size, the BWRX-300 has been designed to use more commercial off-the-shelf equipment than previous BWRs. For instance, the turbine and generator models have been used on many fossil plant projects, such as combined-cycle combustion turbine sites, and can be used for this plant with small modifications. This leads to lower cost.

2.2 Key Features

Key features of the BWRX-300 compared to the ABWR and ESBWR are shown in Table 2-1, *Comparison of Key Features*.

Economic Advanced Boiling **Feature** Simplified Boiling **BWRX-300 Water Reactor** Water Reactor Direct Cycle BWR Plant Type Direct Cycle BWR Direct Cycle BWR Plant Gross Electrical Output ~1,350 MWe ~1,600 MWe ~316 MWe Reactor Thermal Output 4,500 MWth 870 MWth 3,926 MWth Reactor Coolant Reactor Internal **Natural Circulation** Natural Circulation Recirculation Pumps Reactor Operating Pressure 7.2 MPa (abs) 7.2 MPa (abs) 7.2 MPa (abs)

Table 2-1: Comparison of Key Features

Table 2-1: Comparison of Key Features

Feature	Advanced Boiling Water Reactor	Economic Simplified Boiling Water Reactor	BWRX-300
Reactor Vessel Extensive use of forged rings		Extensive use of forged rings	Extensive use of forged rings; integrated isolation valves
RPV Diameter (ID)	7.1 m	7.1 m	4 m
RPV Height (Inside)	21.0 m	27.6 m	27 m
Fuel Type	GE14	GNF2e	GNF2
Number of Fuel Bundles	872	1,132	240
Control Blade Type	Cruciform B ₄ C or Hf	Cruciform B ₄ C or Hf	Cruciform B ₄ C or Hf
Control Rod Drive (CRD) Type	FMCRD	FMCRD	FMCRD
Number of Control Rods	205	269	57
Steam Conditioning	AS-2B Steam Separators Chevron Steam Dryer	AS-2B Steam Separators Chevron Steam Dryer	AS-2B Steam Separators Chevron Steam Dryer
Primary Containment Vessel Type	Reinforced Concrete Containment Vessel	Reinforced Concrete Containment Vessel	Steel-plate Composite Containment Vessel
ECCS	3-Divisional	Passive	Passive
Isolation Makeup Reactor Core Isolation Cooling System		Isolation Condensers, Passive	Isolation Condensers, Passive
Shutdown Cooling	3-Division Residual Heat Removal System Safety-related	Non-Safety related	SC3
Primary Containment Vessel Cooling System	3-Division Residual Heat Removal System	Passive	Passive
Emergency AC Power	3 Safety-related diesel generators	Non-Safety related	Two SC3 diesel generators
Instrumentation and Control Optics, Multiplex, Fiber Optics, Multiple Channel		Digital, Multiplex, Fiber Optics, Multiple Channel, Diverse Analog DL4a System	Digital, Multiplex, Fiber Optics, Multiple Channel, Diverse Analog DL4a System
In-Core Monitor Calibration	e Monitor Calibration Traversing In-core Probe System		Fixed, In-Core GTs
Control Room	Operator Tasked- Based	Operator Tasked- Based	Operator Tasked- Based

3.0 NUCLEAR STEAM SUPPLY SYSTEMS AND COMPONENTS

The BWRX-300 plant is composed of several mechanical systems which are improved for cost and performance to help meet the project design-to-cost objectives.

3.1 Nuclear Boiler System

BWRX-300 is designed with the proven supply chain of the ABWR (*Status Report 98 – Advanced Boiling Water Reactor II (ABWR II)*, Section 2.2 (16)) and predesigned features from the ESBWR (*Status Report 100 – Economic Simplified Boiling Water Reactor*, Sections 2.4, 2.5, 7.3, and 7.4 (17)) for its primary circuit or Nuclear Boiler System (NBS). The NBS consists of three subsystems: RPV system, Main Steam (MS) system, and the NBS instrumentation system.

The primary functions of the NBS are to:

- Deliver steam from the RPV to the turbine MS system
- Receive Feedwater (FW) from the Condensate and Feedwater Heating System (CFS) to the RPV
- Provide overpressure protection of the RCPB
- Provide core support structure to enable the control rods to stop the nuclear reaction when driven in the core by their respective Hydraulic Control Units (HCUs)
- Provide the flow path to enable the core coolant to keep the core cooled using natural circulation

The NBS supports the safety design philosophy for the mitigation of LOCAs. It is built on utilization of inherent margins (e.g., larger water inventory) to eliminate system challenges and reduce number and size of RPV nozzles as compared to predecessor designs. All nozzles are located significantly above the level of active fuel and the flanged Reactor Isolation Valves (RIVs) are closer to the RPV compared to predecessor designs. The relatively large RPV volume, along with the relatively tall chimney region, provides a substantial reservoir of water above the core. With the elimination of large pipes attached to the RPV below core elevation, the BWRX-300 has no core uncovery, even the most limiting LOCA. Thus, there is no concern over peak fuel clad temperature after an accident. The calculated Peak Cladding Temperature for all accident scenarios remains less than 1204 °C (2200 °F). These design features preserve reactor coolant inventory to help ensure that adequate core cooling is maintained. The large RPV volume enhances safety by reducing the rate at which reactor pressurization occurs if the reactor is suddenly isolated from its Normal Heat Sink (NHS).

3.1.1 Reactor Pressure Vessel

The RPV forms a major part of the RCPB, contains the path for reactor coolant flow through the fuel, and generates steam to drive the High Pressure (HP) and Low Pressure (LP) turbines. Flow through the core is by natural circulation; pumps are not required to force reactor coolant through the RPV. Natural circulation is enabled by a tall chimney between the top of the core at the top guide to the bottom of the steam separators. The RPV design is such that the level of all nozzles is located significantly above the top of active fuel.

The RPV is a vertical, cylindrical pressure vessel fabricated with forged rings and rolled plate welded together, with a removable top head, head flange, seals, and bolting. The vessel also includes penetrations, nozzles, and the shroud support. The RPV has a minimum inside diameter of approximately 4.2 m, a wall thickness of approximately 13.54 cm with cladding, and a nominal inner height of approximately 27.36 m. The bottom of the active fuel region is approximately 5.12 m from the bottom of the vessel and the active core is 3.8 m high.

The BWRX-300 RPV assembly, shown in Figure 3-1, *BWRX-300 Reactor Pressure Vessel and Internals*, consists of the RPV with nozzle, integral RIVs, and its other appurtenances, a removable head, the reactor internals, and supports.

The RPV instrumentation monitors the conditions within the RPV over the full range of reactor power operation and shutdown conditions. The RPV, together with its internals, provides guidance and support for FMCRDs.




Figure 3-1: BWRX-300 Reactor Pressure Vessel and Internals

3.1.1.1 Reactor Internals

The major reactor internal components include:

- Core (control rods and nuclear instrumentation)
- Core support and alignment structures (shroud, shroud support, top guide, core plate, control rod guide tube, and orificed fuel support)
- Chimney
- Chimney head and steam separator assembly
- Steam dryer assembly

Except for the Zircaloy in the reactor core, the reactor internals are stress corrosion resistant stainless steel or other high alloy steels. The fuel assemblies (including fuel rods and channels), control rods, chimney head, steam separators, steam dryer, and in-core instrumentation assemblies are removable when the RPV is opened for refueling or maintenance.

The RPV internals are described from the bottom to the top of the RPV below:

- The Control Rod Drive Housings (CRDHs) provide the extension of the RPV pressure boundary at the bottom head for installation of FMCRDs, shown in Figure 3-1. They also support the weight of an FMCRD, control rod, control rod guide tube, thermal sleeve, orificed fuel support, and four fuel assemblies. Finally, they provide the ports for the attachment of FMCRD hydraulic supply lines.
- The control rod guide tube fits in holes in the core plate and rests on the CRDHs that are
 welded to the reactor bottom head. They provide the lateral support and channel water to
 the control rods, shown in Figure 3-1 and Figure 3-2, Cutaway View of Reactor Core, as
 they move up and down within the core to change the reactor power levels. The control
 rod guide tube also provides vertical support to the orificed fuel supports and to four fuel
 bundles landed on the orificed fuel supports.
- The orificed fuel supports, shown in Figure 3-2, rest inside the respective control rod guide tube with a flanged top that sets down onto the control rod guide tube top end to transfer vertical load. They provide a seat for the lower end of each fuel assembly to rest and provide cruciform slots to maintain alignment engagement of a fully withdrawn control rod and guide the control rod blade as it raises or lowers to respectively decrease or increase reactor power. The orificed fuel support slots are crucial to keeping the control blades properly aligned between the four bundles for rapid insertion into the core from fully withdrawn.
- The shroud support is a circular assembly with vertical legs that are welded to the reactor bottom head. The shroud support provides the vertical and lateral support for the shroud and other components like the top guide and core plate. It also supports the chimney and chimney head and steam separator assembly.
- The core plate, shown in Figure 3-2, is at the bottom of the reactor core area. It provides the lateral support for the fuel assemblies and control rods through the orificed fuel support, provides vertical and lateral support for the nuclear instrumentation, and provides vertical and lateral support the startup sources and for the peripheral fuel supports and fuel bundles. The core plate is between the shroud support and the shroud, and these three pieces are bolted together.

The shroud and chimney, shown in Figure 3-1, make up a stainless steel, cylindrical
assembly that provides a partition to separate the upward flow of coolant through the core
from the downward recirculation flow. This partition separates the core region from the
downcomer annulus. The volume enclosed by this assembly is characterized by three
regions.

- The shroud provides the horizontal support for the core. The top guide, shown in Figure 3-2, is at the top of the reactor core. It provides the lateral support for the fuel assemblies, nuclear instrumentation, startup sources, and control rods. The top guide is between the shroud and the chimney barrel, and these three pieces are bolted together.
- The chimney is a long cylinder mounted to the top guide that supports the steam separator assembly, shown in Figure 3-1. The chimney provides additional downcomer height for the driving head necessary to sustain the natural circulation flow. The chimney forms the annulus separating the subcooled recirculation downward flow from the upward steamwater mixture flow exiting the core. The recirculation flow consists of reactor coolant returning from the steam separators and FW makeup. The chimney cylinder is flanged at the bottom and top for attachment to the top guide and the chimney head, respectively.
- The chimney head and steam separator assembly form the top of the core discharge mixture plenum. The discharge plenum provides a mixing chamber to homogenize the steam/water mixture before it enters the steam separators. Individual stainless steel axial flow steam separators are supported on and attached to the top of standpipes that are welded onto the chimney head.
- The steam separators have no moving parts. In each separator, the steam/water mixture
 rising through the standpipe passes through vanes to separate the water from the steam.
 The separated water flows from the lower portion of the steam separator into the
 downcomer region. The separator assembly is removable from the RPV for refueling and
 other in-vessel activities.
- The steam dryer assembly, shown in Figure 3-1, completes the task of removing the moisture from the steam before it exits the reactor. The steam dryer is supported by a set of four brackets equally spaced around the vessel shell internal wall. The dryer support ring rests on these brackets. Additional hold-down brackets are mounted inside the vessel head to restrain vertical movement of the dryer under seismic or dynamic loads. These four hold-down brackets are installed so that they are over the lifting lugs of the steam dryer. Horizontal motion due to seismic or dynamic loads is limited by a set of four seismic blocks mounted to the steam dryer support ring. The moisture content is lower than 0.1% at 100% reactor power when the steam leaves the reactor on its way to the turbine.




Figure 3-2: Cutaway View of Reactor Core

3.1.1.2 Reactor Isolation Valves

The BWRX-300 RIV design is a critical part of the overall LOCA mitigation strategy for the BWRX-300 design. A fundamental design goal of the BWRX-300 is to be designed and licensed to eliminate the non-isolable LOCA for pipe breaks greater than 19 mm (3/4 inch) nominal pipe size. This innovation enables simpler passive safety systems, a more compact containment that is dry, and a simpler RB compared to prior LWR designs.

The BWRX-300 design eliminates the traditional non-isolable large break LOCA by utilizing novel, redundant RIVs integral to the RPV. This feature allows the RPV to be isolated automatically, quickly stopping leakage from the vessel following a downstream pipe break. The BWRX-300 RPV isolation valve design has the following design features:

- Dual quarter turn isolation valves integrally attached to each RPV process nozzle > 19 mm
- Redundant, leak proof valves which are CCF proof and fail-safe in that loss of power or hydraulics/air results in the valves closing
- No incident of a single component prevents the RIVs from performing their designed function
- Automatically actuated using SC1 controls

SCs for Instrumentation and Control (I&C) are described in Section 6.0, *Instrumentation and Control Systems*.

The RIVs are on the RPV nozzles for the MS subsystem, the Reactor Water Cleanup System (CUW), the supply and return lines of the ICS system, the Head Vent, and the FW System.

The RIVs close to limit the loss of coolant from large and medium pipe breaks. The RIV concept consists of two RIVs in series. Each of the RIVs is independently able to isolate the line. Generally, upon loss of power, the RPV isolation valves move to the closed position. However, the RIVs for the ICS steam supply and condensate return lines are exceptions. The ICS RIVs remain as-is because they perform safety functions during many transient and LOCA events. The fail-as-is RIVs for the ICS steam supply and condensate return piping automatically close on indication of a break in the ICS train in which the RIV is located.

The RIVs are mounted in a double valve body made from an integral assembly connected via a flange. The valve body or bodies are attached to the RPV using flanged connections. The valve body or bodies are within the ASME BPV Code Section III, Class 1 RPV assembly. For piping that have RIVs, the closest piping terminal end (high stress and fatigue location) to the RPV assembly is located outboard of each set of two in-series RPV isolation valves. Figure 3-3, BWRX-300 Reactor Pressure Vessel Isolation Valve Design, shows Reactor Isolation Valve views using a flanged connection.




Figure 3-3: BWRX-300 Reactor Pressure Vessel Isolation Valve Design

3.1.1.3 Reactor Pressure Vessel Head Vent Subsystem

The BWRX-300 RPV design includes internal piping routed from the inside of the top of the RPV steam dome area to below the RPV shell flange. The Head Vent piping penetrates the RPV through a nozzle on the side of the reactor with two flange mounted RIVs in series with a single valve body; this eliminates external piping that is to be removed/disconnected during each refueling outage.

During normal operations, non-condensable gases in the steam dome area are vented through the Head Vent piping to a Main Steam Line (MSL). During reactor shutdown periods, reactor water level can be measured using the vent connection as the upper tap for the level instrumentation sensor. During cold shutdown, filling of the vessel for flood up and hydrostatic testing is performed using the RPV vent. Non-condensable gases are vented to the drywell equipment sump while the connection to the steam line is blocked. When draining the vessel during shutdown, air enters the vessel through vacuum breakers in the vent line.

3.1.2 Main Steam Subsystem

The MS subsystem consists of two steam lines from the discharge flange of the outboard Main Steam Reactor Isolation Valves (MSRIVs) to the Turbine Stop Valves (TSVs), the turbine bypass valves, the MSL drains, and other load isolation/maintenance valves. The supply lines to these loads, all connecting branch lines up to and including their respective isolation valves, and all associated piping supports are also part of the MS subsystem.

The MSL drains drain any condensate from the MSLs to the main condenser during startup, low power operation, normal power operation, and shutdown. A reduction in power to a low-level result in the automatic opening of the air-operated drain line valves, thereby establishing drain flow to the main condenser.

3.1.3 Nuclear Instrumentation

The nuclear (core) instrumentation consists of the Local Power Range Monitors (LPRMs), GTs, and Wide Range Neutron Monitors (WRNMs).

The are 13 vertical strings of LPRMs arranged radially throughout the BWRX-300 core. Each string has four LPRMs equally spaced vertically and equally along height of the core. The LPRM strings are located between the corners of the fuel channels of the adjacent four fuel bundles. The total number of 52 LPRMs are divided into the three divisions such that each division gets an approximately equal number of vertical and radial LPRM core locations.

GTs are in-core devices that convert local gamma flux to an electrical signal; gamma flux is representative of core thermal power. It represents a completely diverse technology to the neutron detecting LPRMs. The GTs are co-located in the instrument tubes with the 13 LPRM strings. The GTs are axially located next to each of the four LPRMs, between each LPRM and between the lowest LPRM and core bottom. This totals eight GTs in each of the 13 LPRM strings. There are a total of 104 GTs measuring dispersed radial and axial local power in the core.

The ten WRNM detectors are distributed radially in the core at fixed heights. Each detector is sensitive to neutrons from fluxes below criticality to greater than 100% thermal power – a range of over 11 decades. At low power levels, the WRNMs produce pulse signals; as power increases, the signal becomes a voltage level proportional to the power level.

See Figure 3-4, *Axial Sensor Core Placement*, and Figure 3-6, *Core Map and Instrumentation Layout*, for core instrumentation placement. Figure 3-5, *Nuclear Instrumentation Ranges*, illustrates optimal ranges for the BWRX-300 nuclear instrumentation.




Figure 3-4: Axial Sensor Core Placement




Figure 3-5: Nuclear Instrumentation Ranges




Figure 3-6: Core Map and Instrumentation Layout

3.2 Control Rod Drive System

The CRD System includes three major elements: FMCRD mechanisms, HCU assemblies, and the CRDH subsystem.

There are 57 FMCRDs mounted in housings welded into the RPV bottom head. Each FMCRD has a movable, hollow piston that is coupled at its upper end, inside the RPV, to the bottom of a control rod. The piston is designed such that it can be moved up or down, both in fine increments and continuously over its entire range, by a ball nut and ball screw driven by the motor. In response to a scram signal, the piston rapidly inserts the control rod into the core hydraulically using stored energy in the HCU scram accumulator (see cross-section in Figure 3-7, *Fine Motion Control Rod Drive*). The FMCRD design includes an electromechanical brake on the motor drive shaft and a ball check valve at the point of connection with the scram inlet line. These features prevent control rod ejection in the event of an incident in the scram insert line.

In addition to hydraulic powered scram the FMCRD motors also provide continuous electric motor-driven run-in of all control rods as a path to rod insertion that is diverse from the hydraulic powered scram. In the event of a PIE that requires a rapid reactor shutdown, and if the reactor scram fails or is delayed, then the reactor is shut down by the electric motor run-in of FMCRDs function. The FMCRD does not interfere with refueling and is operative even when the head is removed from the RPV.

There are 29 HCUs, each of which provides sufficient pre-charged accumulator water storage to scram two FMCRDs, except for the FMCRD in the center of the core which has its own HCU, at any reactor pressure. Each HCU contains a nitrogen-water accumulator and the necessary valves and components to scram FMCRDs. Additionally, during normal operation, the HCUs provide a flow path for purge water to the associated FMCRDs which then flows into the reactor, adding to reactor coolant inventory.

The CRDH subsystem provides demineralized water that is regulated and distributed to provide charging of the scram accumulators and purge water flow to the FMCRDs during normal operation. The CRDH subsystem is also the source of pressurized water for purging the Shutdown Cooling System pump seals and the NBS reactor water level reference leg instrument lines.




Figure 3-7: Fine Motion Control Rod Drive

3.3 Isolation Condenser System

The ICS consists of three independent trains, each containing a Heat Exchanger (HX) or IC that is submerged in a dedicated pool of water and is connected to the RPV by steam supply and condensate return piping. The complex of ICS pools represents the ultimate heat sink for protecting the reactor core when the main condenser is not available, and the RPV becomes

isolated. Each IC has a capacity of approximately 33 MW (approximately 3.7% of rated thermal power).

When in operation, the ICS removes heat from the reactor coolant and rejects it to the environment. The ICS also reduces increases in steam pressure and maintains the RPV pressure at an acceptable level through decay heat removal. This is accomplished by condensing reactor coolant supplied as steam from the RPV on the tube side of the ICs and then returning the condensate back to the RPV in a closed loop. Heat removed from the steam is transferred by the IC to the water in the pool, and the pools are vented to the atmosphere. The ICs are placed at an elevation above the steam source, causing natural circulation that is driven passively by gravitational force. The arrangement of the IC is shown in Figure 3-8, *Isolation Condenser System*.




Figure 3-8: Isolation Condenser System

One ICS train is needed to mitigate AOOs. Two ICS trains are required for LOCA mitigation (analysis assumes one ICS train has a single incident). With two ICS trains in service, decay heat removal is sustained for seven days without operator action. All three ICS trains are credited for beyond design basis events, and the IC pool inventories can be replenished indefinitely. The heat rejection process is continued beyond seven days when the IC pool inventory is replenished. The ICS pools are located above ground and are not pressurized. Clean makeup water can be added directly to the ICS pools using readily available transportable sources, such as a fire truck.

The ICS may be placed in service manually from the Main Control Room (MCR), automatically by the protection systems signal or by passive means if a loss of Direct Current (DC) power occurs (fail-safe). To place a train of the ICS in service, one of the parallel condensate return valves is opened (or fails open), allowing the standing condensate to drain to the RPV inlet in the chimney region.

3.4 Containment

The BWRX-300 Primary Containment System (PCS) encloses the RPV and some of its related systems and components, provides radiation shielding, and acts as a boundary for radioactive contamination released from the NBS or from portions of systems connected to the NBS inside the containment system. The reduction of potential LOCAs and application of a dry containment eliminates the need for a suppression pool.

The BWRX-300 uses a traditional containment system for the ultimate containment of radioactive materials for various postulated events. The BWRX-300 containment is a vertical cylinder approximately 19 meters outside diameter and 38 meters high. It comprises a Steel-Plate Composite Containment Vessel (SCCV), consisting of steel-plate composite cylindrical wall, basemat, and top slab, and a steel containment closure head. The containment structure is completely enclosed within the deeply embedded RB and includes personnel/equipment hatches, containment penetrations, and other safety components. Figure 3-9, BWRX-300 Dry Containment, highlights important structures and components of the PCS. The SCCV is also integrated with the RB and the integrated structure is supported by a common steel-plate composite basemat.

A core catcher is provided below the RPV for corium to spread and prevent contact with as a mitigating feature following a severe accident. The core catcher is equipped with a corium shield liner manufactured of Zirconia to contain the corium and prevent Molten Core Concrete Interaction (MCCI). The complimentary design feature of containment flooding quenches the spread corium to maintain containment integrity and reduce the environmental release.

The PCS has provisions for personnel access and for habitability during plant outages to perform maintenance, inspections, and tests required for assuring SCCV integrity and reliability, and the integrity and performance reliability of interfacing SSCs contained inside the PCS boundary.

The PCS is designed for a design life of 60 years of operation plus an assumed {20 years} for decommissioning.




Figure 3-9: BWRX-300 Dry Containment

3.5 Containment Cooling System

The Containment Cooling System (CCS) is used to help meet the containment bulk average temperature is maintained according to technical specifications. CCS maintains normal temperature operating envelope in the SCCV to help ensure initial conditions assumed in safety analysis are met and help meet that environmentally qualified equipment is within the design envelope in operating modes where the containment is not open.

The CCS is a closed loop recirculating cooling system with no outside air introduced into the system except during outages. The CCS is comprised of two fully redundant trains of Air Handling Units (AHUs). Each AHU is cooled by a corresponding Chilled Water Equipment (CWE) system train, so that SCCV cooling is still possible even with loss of one train of CWE or one train of CCS.

The SCCV is purged with nitrogen before startup and kept inerted during normal plant operation.

During normal operation, hot nitrogen gas is drawn from the upper containment space over the coils, cooled, and discharged to the common distribution header. At the header, a portion of the cooled nitrogen gas is ducted directly to the CRD area, and the remaining nitrogen is ducted to the upper containment area.

During outages requiring containment entry, the Heating, Ventilation, and Cooling System, supplies filtered, conditioned outside air into the SCCV through piping interface to purge the nitrogen out of the SCCV. In this mode, the SCCV temperature is maintained for human comfort by the CCS.

The CCS does not perform any safety functions but does assist with containment cooldown following a Loss-of-Offsite Power (LOOP) during the period from hot shutdown to cold shutdown and limits containment temperature during LOOP.

3.6 Passive Containment Cooling System

The Passive Containment Cooling System (PCCS) relies on natural circulation to transfer heat from the containment to the equipment pool to maintain containment pressure and temperature within the design limits during accident conditions or loss of active containment cooling. Supply and discharge connections from the pool are connected to closed loop piping within containment. Heat transfer occurs from the containment to the PCCS by natural circulation and condensation.

The PCCS consists of three independent trains of LP HXs that transfer heat from the containment to the equipment pool which is located above the PCS and is filled with water during normal operation.

The equipment pool is vented to the atmosphere. PCCS operation requires no sensing, control, logic, or power actuated devices for operation. The PCCS condensers are closed loop, and the fluid inside does not contact the containment atmosphere. Since there are no containment isolation valves between the PCCS HXs and the containment, the mode is always in "ready standby." The PCCS is in service during normal operation. However, the PCCS does not contribute to the heat removal significantly during normal operation since the containment temperature is maintained by the CCS.

The PCCS becomes effective when steam is discharged into the containment following a pipe break. The steam discharge to containment raises containment temperature and increases the steam content for condensation to occur. Heat transferred to the PCCS from the containment is removed by the natural circulation of water in single phase flow and rejected to the equipment pool.




Figure 3-10: Passive Containment Cooling System

3.7 Boron Injection System

The purpose of the Boron Injection System (BIS) is to introduce sufficient negative reactivity into the reactor primary system to assure a reactor shutdown from the full power operating condition to the cold 20°C (68°F) subcritical state with no control rod motion. The BIS dispenses the minimum required neutron absorber of natural boron using a Boron-10 solution or equivalent into the core zone to meet the minimum shutdown concentration required throughout the core region while providing reasonable margin for leakage or imperfect core mixing.

The system is provided for, and only for, a situation which causes the normal reactor control system to be unable to shut down the reactor. The BIS acts as an emergency backup to the insertion of control rods to provide a diverse means of making the reactor subcritical.

The BIS consists of a storage tank, test tank, injection pump, piping, valves, and I&C necessary to prepare and inject a neutron absorbing solution into the reactor and to test the system. The injection line contains an air-operated injection valve and a check valve as the outboard and inboard containment isolation, respectively.

The BIS is manually initiated from the MCR, as directed by the emergency operating procedures, if the operator believes the reactor cannot be shut down, or kept shut down, with the control rods. Actuation of the system requires a conscious operator action, and the design is such that a single operator can readily initiate the system into the injection mode.

3.8 Reactor Water Cleanup System

The CUW provides blowdown-type cleanup flow for the RPV during reactor power operating mode. Cleanup, or filtration, and ion removal is performed by the Condensate and Feed System (see Section 5.1.4, *Condensate and Feedwater System*). The CUW also provides an over boarding flow path to either the condenser hot well or liquid radwaste directly from the RPV lower region to control water level during startup. CUW suction piping can be used to reduce reactor temperature stratification with reverse flow from the Shutdown Cooling System.

The CUW system consists of one train fed by two suction nozzles located on the RPV. The train's suction is independently connected to RPV penetrations located at about the mid-vessel height and takes suction from nozzles located near the RPV bottom head. The piping from the suction nozzles combines inside containment to form a single line; this line is provided with a containment isolation valve where it penetrates containment. This valve receives signal from the CUW leak detection system and closes upon a leak detection.

Major components of the CUW system are the CUW HX and pressure reduction station. The CUW HX is a Regenerative Heat Exchanger (RHX) cooled by FW flow. The RHX and pressure reduction station are designed to condition the water to acceptable temperatures and pressures for processing to the condensate system or over boarding. The RHX is designed to recover heat back to the vessel. Discharge piping is connected either to a condensate line for the normal CUW function or routed to either the condenser hotwell or liquid radwaste for over boarding.

3.9 Shutdown Cooling System

The Shutdown Cooling System (SDC) provides for decay heat removal when shutting down the plant for refueling or maintenance. The system is also used to reduce RPV inventory and can be used in conjunction with CUW piping to reduce RPV thermal stratification.

The SDC system comprises two independent pump and HX trains. These trains together provide redundant decay heat removal capacity such that each train is designed to remove 100% of decay heat as soon as 4 hours after reactor shutdown. The major components of each train are a pump and an HX, along with valves, piping, I&C, and power inputs. The two trains operating in parallel provide the system's full rated Shutdown Cooling performance. Bypass lines and valves are included around the tube side of each HX to allow bypassing of the HX for SDC functions, such as reducing RPV thermal stratification.

3.10 Isolation Condenser System Pool Cooling and Cleanup System

The primary function of the ICS Pool Cooling and Cleanup System (ICC) is to remove heat from the ICS pools such that the bulk temperature of water in the pools is maintained below Technical Specification (TS) limits and thereby ensuring the readiness of the ICS to perform its Safety Category function. Secondary functions of the ICC include maintaining the cleanliness of the ICS pool water and providing the capability to add clean makeup water during normal reactor operations to offset the minor routine loss of water inventory due to evaporation.

The ICC processes water from the three ICS Cubicle Pools and surrounding Outer Pools to maintain water temperature and quality within the prescribed TS limits established for the plant. The ICC includes two identical, 50% capacity trains, each equipped with a centrifugal pump and frame-and-plate HX to transfer energy from the ICS pools to the Plant Cooling Water System (PCW). The system also includes a single integrated skid-mounted demineralizer to remove soluble and insoluble impurities from the ICS pool water.

3.11 Fuel Pool Cooling and Cleanup System

The primary function of the Fuel Pool Cooling and Cleanup System (FPC) is to provide continuous cooling of the water volume in the fuel pool to remove decay energy from spent fuel, and to provide replacement coolant inventory from a variety of sources to help ensure spent fuel is kept cool and submerged throughout the life of the plant. In addition, the FPC includes demineralization and particulate filtration to maintain coolant quality and to reduce general area dose. The FPC can be realigned to provide cooling and cleanup to the reactor cavity and equipment pools, as necessary.

The FPC consists of two trains of equipment, each with a pump, demineralizer, and HX. The capability to bypass the demineralizer while providing active cooling to support restoration of the pool temperature from conditions exceeding the demineralizer operational temperature limits is provided. Each set of components are placed in parallel to provide single train operation and cross connecting of trains should a component fail. A single train is sufficient to prevent bulk boiling in the fuel pool. If both trains are rendered inoperable, the fuel pool is sized such that it can retain sufficient coverage of the fuel for seven days, and the FPC can provide makeup capacity from various sources to help ensure pool level during off-normal conditions.

The FPC takes suction from two skimmer surge tanks, which remove coolant from the tops of the three pools, passes it through the system, and returns it through spargers at the bottom of each pool, which are protected by anti-siphon devices to prevent inadvertent draining of the pools if a breach of the FPC occurs. The demineralizer allows for removal of small particulate matter through back-washable filters, with ionic cleanup performed via deep bed demineralization using mixed anion and cation bead resin.

4.0 FUEL AND FUEL CYCLE

The BWRX-300 core design includes a 240-bundle configuration. The core uses Global Nuclear Fuel's GNF2 (*GNF*2 (8)) fuel assemblies because they have low hydraulic resistance, which benefits natural circulation. The fuel rod configuration (shown in Figure 4-1, *GNF2 Four-bundle Cell and Lattice Array*) has equal spacing between the control rod and non-control rod sides of the fuel bundle (N-lattice). This configuration provides more shutdown margin for variations in burnup histories imposed by load following.




Figure 4-1: GNF2 Four-bundle Cell and Lattice Array

4.1 Core Configuration

The reactor core of the BWRX-300 is arranged as an upright cylinder containing fuel assemblies located within the core shroud. The coolant flows upward through each fuel assembly. The BWRX-300 reactor core includes fuel assemblies, control rods, and nuclear instrumentation. The fuel assembly and control rod mechanical designs are the same as existing, operating GE BWRs.

4.2 Fuel Assembly Description

A BWR fuel assembly consists of a fuel bundle and a coolant channel. The fuel bundle contains the fuel rods and the hardware necessary to support and maintain spacing between fuel rods. The channel is a Zircaloy box surrounding the fuel bundle and directing core coolant flow through the bundle; it also serves to guide the movable control rods.

The BWRX-300 GNF2 design is a 10x10 array of 78 full-length fuel rods, 14 part-length rods and two large, central water rods. The low core power density of BWRX-300, enhanced natural circulation flow, and higher FW temperature maintains thermal-hydraulic stability.

Figure 4-2, *GNF2 Fuel Bundle* shows the GNF2 fuel bundle design with major components identified. This figure shows the bundle in a horizonal orientation, but during storage and operation, the bundles are in a vertical position.




Figure 4-2: GNF2 Fuel Bundle

The cast stainless steel lower tie plate has a conical section to promote seating into the orificed fuel support. Multiple spacer grids along the length of the fuel assembly maintain the proper fuel rod spacing. A debris filter in the lower tie plate prevents foreign material from entering the flow channel and potentially damaging the fuel cladding. The cast stainless steel upper tie plate is also a spacer grid and provides the bundle lifting handle.

The fuel assembly is held together by eight tie rods located around the periphery of the fuel bundle (see Figure 4-1 for cross-sectional view for part, full, tie, and water rod arrangement within a bundle and for bundle orientation within a four-bundle cell). In all but 12 peripheral locations, fuel bundles are arranged in a four-bundle grouping around a control blade. Figure 4-1 shows a horizontal cross-section of four-bundle cells. The four squares with rounded corners are the channels. The black cross that the four bundles surround is the control blade.

4.3 Fuel Handling and Refueling Process

The BWRX-300 fuel handling and refueling process takes advantage of historical BWR practices. The refueling process is an intricately scheduled series of tasks to disassemble/assemble the containment head, RPV head, remove/replace the RPV internals to access the fuel assemblies and remove/replace/shuffle the fuel assemblies. Figure 4-4, *Refueling Floor (Reactor Building Roof removed)*, depicts the refueling floor.

The RB includes a refueling platform (gantry crane) for fuel movement and servicing. The refueling platform spans the RPV and storage pools on tracks in the refueling floor. A telescoping mast and grapple suspended from a trolley system lift and orient fuel assemblies for placement either in the core or in storage racks in the fuel pool.

A position indicating system is provided to locate the grapple over the vessel core and prevent collision with pool obstacles. The mast grapple has redundant features so that no single component incident results in a fuel bundle drop. Multiple interlocks are provided on the refueling machine to prevent mishandling of the fuel assemblies.

Storage racks provide for the short-term and long-term storage of new or used fuel and associated equipment. The fuel storage racks are spaced to prevent inadvertent criticality. Fuel racks are in the fuel pool in the RB, as shown in Figure 4-3, *Fuel Pool Arrangement*. The racks are top loading, with a fuel assembly bail extended above the rack. The fuel racks' storage capacity is approximately 275% of a complete reactor core or 600 fuel storage positions. This capacity is equivalent to eight years of refueling operations plus a full core off-load and new fuel storage. The fuel racks maintain a subcriticality margin of at least 5% Δ k/k under dry or flooded conditions. The rack arrangement prevents accidental insertion of fuel assemblies between adjacent racks and is spaced to allow flow between assemblies such that pool water does not exceed 100 °C.

Additional long-term storage of used fuel using dry cask storage units located in an on-site independent spent fuel storage installation facility may be available. A characteristic independent spent fuel storage installation facility has a capacity of 28 canisters at 89 bundles each for a total of 2492 fuel bundles. BWR plant fuel canister movement activities are typically scheduled every 3-4 years and performed while the plant is at power.

Upon completion of fuel movement operations, procedures require verification of each individual fuel assembly serial number and verify each is installed in the correct position and orientation consistent with the core reload analysis.

After fuel installation verification, the RPV and containment are reassembled, and leak tests are performed to verify that primary pressure boundary and containment pressure boundaries are intact. The reactor cavity pool is then flooded, and the reactor is readied for heat-up, criticality and power ascension.

Refueling outages are 10-15 days based on the number of fuel assemblies to be replaced considering plant cycle duty. The cycle times can vary between 12 and 24 months depending on the operating strategy. About 32 bundles are replaced following a 12-month cycle and 72 bundles following a 24-month cycle.

A major equipment inspection outage of 25 days is anticipated every 120 months to perform turbine inspections and in-service inspection of the RPV and internals.




Figure 4-3: Fuel Pool Arrangement




Figure 4-4: Refueling Floor (Reactor Building Roof removed)

5.0 BALANCE OF PLANT

The BWRX-300 Balance of Plant (BOP) systems are configured like those in use throughout the BWR fleet adjusted for gross power output. The gross power of ~315 MWe eliminates the need for custom designed turbines and generators as standard frame sizes are available from turbine generator set manufacturers.

5.1 Steam and Power Conversion System

5.1.1 Main Steam

The BWRX-300 MS subsystem is part of the NBS (see Section 3.1.2, *Main Steam Subsystem*) and consists of two steam lines from the discharge flange of the outboard MSRIVs (Figure 5-1, *BWRX-300 Reactor Building Main Steam 3D View*) to the TSVs (Figure 5-2, *BWRX-300 Turbine Building Main Steam Top 3D View*), the turbine bypass valves, the MSL drains, and other load isolation/maintenance valves. The supply lines to these loads, all connecting branch lines, up to and including their respective isolation valves, and all associated piping supports are also part of the MS subsystem.

The BWRX-300 design includes an outboard Main Steam Containment Isolation Valve (MSCIV) (Figure 5-1) on each MSL. The MSCIVs provide the isolation of the containment in the event of accidents or other conditions and prevent the unfiltered release of containment contents that exceed appropriate limits. This containment isolation is single incident proof. The MSCIVs are fast-closing, fail-closed valves.

The MS flow restrictors are in the RPV MS nozzles. The function is to limit the overall steam flow through one steam line when the steam flow exceeds preselected operational limits (if a large break of a MSL is sensed) and the corresponding MSRIVs and MSCIVs have not closed. The MS flow restrictor provides LP sensing taps for instrumentation lines for differential pressure transmitters that are used to measure steam flow. MS flow is measured through the MS nozzle venturis using Bernoulli's equation of differential pressure to derive the MS mass flow.

The MSL drains remove any condensate from the MSLs to the main condenser during startup, low power operation, normal power operation, and shutdown. A reduction in power to a low-level, results in the automatic opening of the air-operated drain line valves, thereby establishing drain flow to the main condenser.

The turbine bypass valves are opened by I&C system when the actual steam pressure exceeds the steam pressure needed by the turbine. One or two bypass valves may be modulated as required in response to changes in the bypass demand. Bypass steam is discharged to the main condenser.




Figure 5-1: BWRX-300 Reactor Building Main Steam 3D View




Figure 5-2: BWRX-300 Turbine Building Main Steam 3D View

5.1.2 Turbine Generator

A typical steam turbine, such as planned for BWRX-300, is shown in Figure 5-3, *Steam Turbine*. The turbine is a 3000/3600 revolutions per minute, single-shaft, tandem compound, impulse-reaction, two-stage reheat, condensing steam turbine (*Steam Turbines for Fossil, Nuclear, and Renewable Applications* (9)). The turbine generator, associated piping, and valves, are located completely within the Turbine Building (TB).





Figure 5-3: Steam Turbine

Figure 5-4: TOPAIR Generator

Two hydraulically operated TSVs, and control valves (four valves total) admit steam to the HP turbine. The primary function of the MS TSVs is to isolate the MS from the turbine and quickly shut off the steam flow to the turbine under emergency conditions. The primary function of the control valves is to control steam flow to the turbine in response to the Turbine Generator Control System. In addition to the normal speed control function provided by the Turbine Generator Control System, a separate and redundant turbine overspeed protection system is included to reduce the possibility of turbine rotor incident and turbine missile damage.

The HP turbine receives steam through two steam leads, one from each control valve outlet. The steam is expanded axially across several stages of stationary and moving blades. Extraction steam from the HP turbine is used to supply the fifth stage of FW heating and Moisture Separator Reheater System (MSR) first stage reheater heating steam. HP turbine exhaust steam is collected in a cold reheat pipe and routed to the MSR inlet.

Two LP turbines coupled together with the HP turbine shaft convert thermal energy into mechanical rotational energy to drive the generator. Each LP turbine receives hot reheat steam from its connected MSR outlet through the intermediate stop and intercept valves. Each LP turbine is a double flow with six extraction points for FW heating. Each LP turbine exhausts directly to the main condenser connected underneath each LP turbine.

The main turbine is equipped with a turning gear, which is used to rotate the turbine generator shafts slowly and continuously, as needed, when the main turbine is not in service, such as the early part of turbine warming and after the rotor has stopped at shutdown.

The turbine gland seal steam supplies sealing steam to the turbine shaft/casing penetrations and to the valve stems of the turbine stop and control valves, bypass valves and intermediate stop and intercept valves to prevent the escape of radioactive steam and to prevent air in-leakage through sub-atmospheric turbine glands.

The Turbine Lube Oil System (TLOS) supplies the lube oil to the turbine, generator, and exciter brush bearings. The TLOS skid includes redundant AC pumps and a DC pump to continuously supply oil to the bearings to provide asset protection. The lube oil skid also contains storage tank and HXs which support the TLOS. An oil conditioning system is provided with TLOS.

A typical TOPAIR generator, such as planned for BWRX-300, is shown in Figure 5-4, *TOPAIR Generator*. The generator is a direct driven, three-phase 50/60 Hz, synchronous generator with an air-cooled armature winding and rotor. The generator shaft is connected to the main turbine equipment system, as the shaft (rotor) spins within the generator frame (stator) electricity is produced. There are more than 3,570 TOPAIR units in operation (*Air-Cooled Generator (GEN-A)* (6)).

5.1.3 Main Condenser

The Main Condenser and Auxiliaries (MCA) System is the heat sink for the power generation and normal reactor cooldown and plant startup activities. The MCA System consists of the main condenser, two Steam Jet Air Ejector (SJAE) skids, and two condenser vacuum pump skids as well as associated piping, valves, instrumentation, and controls. The main condenser is a single-pressure, two-shell unit. Each shell is located beneath its respective LP turbine. The two condenser shells operate at similar pressures and drain to hot wells that are cross connected. Circulating water flows through each of the two single-pass tube bundles to condense the turbine exhaust steam into the hot wells.

The main condenser receives and condenses turbine exhaust steam and turbine bypass steam during all modes of operation. The main condenser provides hold-up for N16 decay and supplies condensate to the condensate pumps. The main condenser also serves as a collection point for other steam cycle miscellaneous drains, vents, and relief valve discharges. The condenser is cooled by the Circulating Water System configured as either a closed system (i.e., heat rejection via cooling towers) or an open system (i.e., rejects heat to an appropriately sized body of water).

Two 100% capacity SJAEs are used to maintain the turbine backpressure and remove non-condensable gases from the main condenser. Non-condensable gases extracted from the condenser are exhausted to the Offgas System. During startup, two condenser vacuum pumps draw the initial condenser vacuum and exhaust gases to the TB heating, ventilation, and air conditioning system.

5.1.4 Condensate and Feedwater System

The CFS contains two condensate pumps, two reactor FW pumps, three stages of LP closed FW heaters, and three stages of HP FW heaters. The condensate pumps are each 100% capacity. The LP FW heaters are arranged with two 50% capacity duplex FW heaters in parallel and the third stage 100% capacity heater in series. The two reactor FW pumps are driven by electrical motors and powered by adjustable speed drives, each is 100% capacity and used to maintain RPV water level. The three HP FW heaters are arranged in series. There are bypass valves around each FW heater.

CFS provides a vent and drain path for condensate, vapor, and non-condensable gases during all modes of system operation to maintain level in the FW Heaters and MSR drain tanks. The final stage HP FW heater accommodates final FW temperature control during power maneuvering.

The Condensate Filters and Demineralizers System (CFD) purifies the condensate to maintain reactor FW purity. The CFD uses filtration to remove suspended solids, including corrosion products, and ion exchange resin to remove dissolved solids from condenser leakage and other impurities. The CFD is a full-flow system that consists of high efficiency backwash type filters followed by mixed bed demineralizers.

5.2 Balance of Plant Auxiliary Systems

5.2.1 Circulating Water System

The Circulating Water System (CWS) provides cooling water to the main condenser and transfers heat from the condenser to the environment through the NHS. The CWS also supplies cooling water to reject the heat loads from the PCW HXs through the NHS. All CWS pumps are in the NHS structure.

The CWS has two subsystems: the main condenser supply and the PCW supply. The main condenser supply uses 2x50% pumps to provide cooling water to the MCA during all modes of condenser heat removal. A hot circulating water return line is provided to recycle water returning from the condenser in cold weather conditions as required to prevent freezing in the NHS structure.

The PCW system consists of two trains, each containing one pump and one HX, that address the reactor component and turbine component cooling loads. The plant cooling water supply uses 2x100% pumps to provide cooling water to the PCW HXs for all normal and abnormal operating modes. The PCW system provides cooling water to non-safety components in the BWRX-300 plant and provides a barrier against radioactive contamination of the CWS.

The PCW supplies cooling water for two subsystems, Reactor Component Cooling Water Subsystem (RCCWS), and Turbine Component Cooling Water Subsystem (TCCWS).

The RCCWS piping distribution consists of two redundant piping distributions that support all RB equipment cooling functions, plant pneumatic system, and any equipment located outside the RB associated with reactor cooling activities.

The TCCWS piping distribution is a single piping distribution that serves all equipment in the TB that does not support reactor cooling functions.

Although the PCW supports all plant equipment cooling functions, the design redundancy and isolation capability is centered around the ability to provide a redundant cooling supply to nuclear systems. Two independent cooling equipment trains with one pump and HX in each train are provided to satisfy the need for redundant cooling supplies to nuclear systems in the redundant RCCWS piping distribution and the single TCCWS piping distribution.

These independent trains are cross connected using manual crossties to allow for online maintenance. If necessary, the TCCWS can be isolated from each RCCWS by closing the supply and return header valves on each train, and each RCCWS train operates independent of the other.

5.2.2 Chilled Water System

The CWE provides chilled water cooling to the Heating Ventilation and Cooling Systems throughout the plant and to the CCS in the RB.

The CWE is a closed loop chilled water system that supplies chilled water to various non-safety category function AHU cooling coils and plant equipment coolers in the TB, Radwaste Building (RWB), RB, and Control Building (CB). Heat absorbed by the CWE is rejected from the CWE chiller condensers to atmosphere above the Radwaste Building.

The CWE is comprised of four CWE air-cooled chillers, four CWE pumps, one expansion tank, four air separators, one chemical bypass feeder, one glycol auto-fill unit, piping, valves, instruments, and controls.

Each chiller has its own dedicated pump. Four by 33% (4X33%) capacity chiller/pump combinations are provided for all plant chilled water use and two of the four chiller/pump combinations are part of the D-in-D protection functions.

6.0 INSTRUMENTATION AND CONTROL SYSTEMS

6.1 **Instrumentation and Control Design Architecture**

The BWRX-300 I&C system (also referred to as the Distributed Control and Information System (DCIS)) is used to monitor and control most plant systems, provide alarms and recording, and provide MCR and Secondary Control Room (SCR) operator interfaces. BWRX-300 design provides appropriate hardware safety classifications per the Safety Strategy described in Section 1.2, Safety Concept and Defense-in-Depth reliability objectives (e.g., no single incident prevents performance of a safety function, and no single incident causes a departure from normal power operation), and cyber security.

The following platforms are selected for use in BWRX-300 I&C systems:

- a. Safety Class 1 (SC1): NUMAC Platform 2.0 digital controllers
- b. Safety Class 2 (SC2): Mark VIeS¹ digital controllers
- c. Safety Class 3 (SC3) and Non-Safety Class (SCN): Mark VIe digital controllers

The NUMAC platform builds on two generations of development and was originally created in 1985 as a digital control system replacement for legacy analog nuclear controls. Since 1985 there have been over 170 digital upgrades in seven countries across 59 BWRs. The Primary Protection System architecture is designed for system dependability (trip when required) and reliability (prevent unnecessary trips) by implementation of a 2 out of 3 trip logic for both failsafe and fail-as-is applications on three independent divisions.

Mark VIe and Mark VIeS are stand-alone, single-board industrial automation process controllers used to provide programmable or fixed process manipulation of physical plant equipment, signals, or control loops. These controllers continuously execute application code in real-time, updating hardwired inputs and outputs, sharing network data and information. The devices are key to plant process automation of the DCIS. IEEE compatible tools are to be used to configure, program, and monitor process hardware, application code, system functions, diagnostics, and health.

Figure 6-1, BWRX-300 Distributed Control and Information System Communication Diagram provides a relationship diagram of the control systems that are defined in Table 6-1, Safety Classification of Distributed Control and Information Systems.

¹ Mark VIe and Mark VIeS are trademarks of GE and/or its affiliates.




Figure 6-1: BWRX-300 Distributed Control and Information System Communication Diagram

Table 6-1: Safety Classification of Distributed Control and Information Systems

Safety Class (1) / Defense Lines	Main Parts List Identifier and System Name	
SC1/DL3	C10 - Primary Protection System	
SC2/DL4a	C20 - Diverse Protection System	C22 - Fine Motion Control Rod Drive (FMCRD) Motor Control System
SC3/DL2 and DL4b	 C30 - Anticipatory Protection System C31 - Reactor Control System C32 - Reactor Auxiliaries Control System C33 - Equipment Cooling and Environmental Control System C34 - Electrical Power Supply Control System C35 - Reactivity Monitoring Systems 	 C36 - Plant Data Acquisition, Data Communications, and Normal Operator Interface System C38 - Turbine-Generator Control System C37 - Control and Monitoring System for DL4b Functions C39 - Normal Heatsink and Condensate/Feedwater (FW) Control System
SCN	 C40 - Investment Protection System C41 - Plant Performance Monitoring C43 - Water Chemistry 	 C44 - Effluent Cleanup Control System C45 - Network Communications and Operator Interface System

⁽¹⁾ These are the overall safety classifications assigned to the system, but they can perform functions for multiple safety categories.

6.2 Main Control Room

The MCR is in the CB. The MCR is the primary location for plant monitoring and control during normal, abnormal, and emergency conditions. The MCR includes controls, indications, and alarms that enable operators to perform the defined set of functions during normal operation modes and PIE conditions. It is expected that the safety and Human Factors Engineering (HFE) analyses being performed as an integral part of the design of the BWRX-300 is to dictate a requirement for an alternate control location; as such, the current concept design includes the SCR. In the event the MCR becomes uninhabitable, or is expected to become unhabitable, or if functionality is unacceptably impaired, personnel are to move to the SCR. The intended functionality of the SCR is to maintain the unit in a safe shutdown condition with the capability to place the unit in a safe shutdown condition. It is not the purpose of the SCR to allow continued operation of the plant at power. Egress from the MCR and access to the SCR is designed such that required minimum operations staffing can safely transition from the MCR to the SCR.

The MCR is designed with Human-System Interface (HSI) to support tasks such as:

- 1. Assessing the overall status and performance of the plant in any condition and providing necessary information to support operator actions.
- 2. Monitoring the status and trends of key plant parameters (such as reactor power and rates of power change).
- 3. Operating the plant safely during all operational states, automatically or manually.
- 4. Taking measures to maintain the plant in a safe state or to bring it back into a safe state after design basis events and DECs.
- 5. Maintaining the plant within the specified limits and conditions for the parameters associated with plant systems and equipment.
- 6. Monitoring for incident of critical instrumentation and equipment.
- 7. Confirming safety actions for the actuation of safety systems are automatically initiated when needed and that the relevant systems perform as intended.
- 8. Determining the need and the time for manual initiation or intervention of specified safety actions.
- 9. Implementing emergency operating procedures, Emergency Mitigating Equipment guidelines, and severe accident management guidelines.

The design provides user selectable display screens and user-defined trending and parameter value monitoring. A robust visual and audible alarming system is provided to alert operators when value thresholds are exceeded. Considering the control technology, the design supports query of control input status (e.g., interlocks, start permissive, auto-start signals) at the point of operation. The Safety Parameter Display System is integrated in the overall MCR HSI designs.

Figure 6-2, *Main Control Room and Surrounding Areas Layout (Top View)* provides an overview of the MCR layout.




Figure 6-2: Main Control Room and Surrounding Areas Layout (Top View)



Figure 6-3: Main Control Room and Surrounding Areas Layout (Side View)




Figure 6-4: Group View Display System Concept (Forward View)

6.3 Secondary Control Room

The SCR is in the RB. The SCR includes the required HSI that enable operators to perform the defined set of functions required for responding to the identified plant events and conditions for which the MCR cannot be used.

The SCR is designed in accordance with current international best practice codes and standards for control room design, integrating results from HFE analyses and specified HFE design requirements.

The SCR is utilized to perform the functions required to keep the plant in a safe state when the MCR is unavailable. The required functions are derived from a safety and HFE analyses.

The SCR includes suitable facilities for habitability and well as workspace for tasks to support required usage. The SCR contains a suitable supply of food and water. The SCR also contains adequate space and provisions for sleeping as required by the postulated scenarios in which it is used.

7.0 ELECTRICAL SYSTEMS

The BWRX-300 Electrical Distribution System (EDS) is an integrated power supply and transmission system. The EDS is arranged like the DCIS with three safety classified segments and an SCN segment with appropriate levels of hardware and software quality corresponding to the system functions they control and their DL. The BWRX-300 EDS are separated according to SC and DL. See Figure 7-2, *Electrical Distribution One-Line Diagram*.

The electrical subsystems are grouped based on safety classification, as shown in Figure 7-1, *Electrical System Architecture.*




Figure 7-1: Electrical System Architecture

Each subsystem has appropriate levels of hardware and software quality (corresponding to the systems they power) to provide power to plant lo ads and a transmission path for the main generator to the utility switchyard/grid. The EDS is monitored and controlled by plant operators from the MCR. Various segments of the EDS can operate independently.

Power is supplied to the plant from an offsite power source, the grid, and is called the "Normal Preferred" power source. The loss of the preferred source may be referred to as a Loss of Preferred Power or a LOOP. The terms may be used interchangeably. The power source is designed to provide reliable power for the plant auxiliary loads. The Preferred Power Supply consists of the Normal Preferred source and includes those portions of the offsite power system and the on-site power system required for power flow from the offsite transmission system to the medium voltage A and B busses.

The on-site AC power system consists of SCN, SC1, SC2, and SC3 power systems. The off-site power source provides the Normal Preferred and Alternate Preferred AC power to SCN, SC1, SC2, and SC3 loads. In the event of total LOOP sources, two on-site independent SC3 Standby Diesel Generators are provided. There are two independent SC2 DC load groups and one SC3 DC load group, each with an uninterruptible power supply to provide power to the respective SC2 and SC3 loads.

The emergency power systems consist of three independent SC1 DC divisions with uninterruptible power supplies to provide power to SC1 loads.

The electrical system is designed with sufficient capacity to meet load requirements to support FSFs. The design incorporates an appropriate D-in-D strategy to help meet availability and reliability of the supported systems.

The function of the highest SC BWRX-300 electric subsystem is to provide power to the highest SC I&C system and any mechanical components needed to support the FSFs.

SC1 batteries in the R10 subsystem are designed to provide backup power for at least 72 hours. The external connections provide for connection of Emergency Mitigating Equipment (also known as FLEX equipment) as needed.

In addition to the safety design criteria and rules and regulations, the following issues specific to the BWRX-300 electrical power systems are included:

- The design of the EDS is to provide for reliable power supply to all SC1, SC2 and SC3 loads during normal conditions.
- The EDS is divisionalized to help ensure that a division can be taken out of service and not disrupt the operations of the plant.
- Battery power is provided to help ensure that monitoring equipment can be powered for at least 72 hours following a Design Basis Event.
- SC3 Standby Diesel Generators are provided to supply backup power to loads.
- The BWRX-300 EDS has been designed to not be required to shut down and cool down the reactor following a Design Basis Event.




Figure 7-2: Electrical Distribution One-Line Diagram

8.0 RADIOACTIVE WASTE MANAGEMENT SYSTEMS

8.1 Discharges During Normal Operation

The types of radwaste discharge during normal operations are well understood for BWRs. The BWRX-300 incorporates decades of lessons learned from the operating fleet to reduce radwaste amounts. The following summarizes types of radwaste generated during normal operation:

- Liquids: BWRX-300 is designed to be a zero-discharge plant for liquid radioactive wastes during normal operations. During outages when a large amount of discharge water inventory is generated by equipment decontamination, the plant may discharge up to 2 m³/hr with adequate dilution flow to meet USNRC Code of Federal Regulations (CFR) Title 10, "Energy." GVH is expected to reconcile to the requirements of other jurisdictions.
- Solids: BWRX-300 is estimated to generate about 36 m³ of low-level wet radwaste per year for disposal of resins and other materials used to filter the water from the condenser and liquid waste cleaning systems. Operations and maintenance are estimated to generate up to 148 m³, prior to compaction or incineration of very low solid radwaste such as heating, ventilation, and air conditioning filters, paper, and plastic materials per year.
- Gaseous: BWRX-300 normal offgas flow is estimated to be less than 15 liters per second discharged from the plant stack at a height of approximately 35 m. The plant is designed to meet the dose limits of USNRC 10 CFR 20, U.S. Code of Federal Regulations, "Standards for Protection Against Radiation," Part 20, Chapter 1, Title 10, "Energy." (22) and 10 CFR 50 Appendix I, U.S. Code of Federal Regulations, "Numerical Guides for Design Objectives and Limiting Conditions for Operation to Meet the Criterion "As Low As Reasonably Achievable" for Radioactive Material in Light-Water-Cooled Nuclear Power Reactor Effluents" (3) and is expected to meet the requirements of other regulatory jurisdictions.

8.2 Liquid Waste Management System

The Liquid Waste Management System (LWM) receives, handles, stores and processes potential liquid radioactive waste generated as the result of normal plant operation, including AOOs.

The filtered water is reused in the plant. The LWM consists of the collection tanks, sample tanks, filtration skids, Refueling Water Storage Tank, Condensate Storage Tank (CST), and associated pumps/piping/instrumentation. Liquid wastes are sent to the collection tanks located in the Radwaste Building via the Equipment Floor Drain System.

The LWM normally operates on a batch basis. Each batch is sampled to determine the concentrations of suspended solids and chemical contaminants. The sampling is performed from sample ports downstream of the collection and sample tanks and analyzed in the lab of the Radwaste Building. Processed liquid waste that meets effluent criteria are pumped into the CST for reuse. Accidental discharge is monitored by the Process Radiation Monitor system through detection and alarm of abnormal conditions and by administrative controls.

The intent of the filtration and processing of all liquid radwaste is to recycle all processed water back to the CST to maintain zero liquid release.

8.3 Solid Waste Management System

The Solid Waste Management (SWM) system controls, collects, handles, process, packages, and temporarily stores solid waste generated by the plant prior to shipping the waste offsite. The SWM system processes filter backwash sludges, charcoal media, and bead resins generated by FPC, ICC, and CFD.

Contaminated solids such as high efficiency particulate air and cartridge filters, rags, plastic, paper, clothing, tools, and equipment are also disposed of in the SWM system.

The SWM system may also receive, process, and dewater solid radioactive waste inputs for permanent offsite disposal. Liquids from the SWM system are sent to LWM for processing.

System components are designed and arranged in shielded enclosures to reduce exposure to plant personnel during operation, inspection, and maintenance. Tanks, processing subsystems equipment, pumps, valves, and instruments that contain radioactivity are in controlled access areas.

Protection against accidental discharge is provided by steel liners in the tank cubicles, detection, and alarm of abnormal conditions, and augmented by administrative controls.

To the maximum extent practicable, mixed waste and non-radioactive hazardous waste are kept out of the SWM. Mixed wastes and potentially radioactive oily wastes are collected primarily in 55-gallon (208-liter) collection drums and sent offsite to an appropriately permitted vendor processor. However, should circumstances dictate the storage or disposal of larger quantities of mixed waste, other approved containers can be used.

In each tank cubicle in the RWB, a small sump with a level alarm is provided for leak detection.

8.4 Offgas System

The Offgas System (OGS) processes and controls the release of gaseous radioactive effluents to the area of the site to limit personnel exposure to radioactive gases as low as reasonably achievable. The OGS holds and allows for the decay of radioactive gases in offgas from the main condenser. OGS delays and filters offgas process steam containing the radioactive isotopes krypton, xenon, iodine, hydrogen, nitrogen, and oxygen to achieve decay before discharge from the plant.

During normal plant operation, non-condensable gases develop in the reactor steam. These need to be removed to maintain turbine efficiency. The gases are drawn from the main condenser via the SJAEs. The mixture is then passed through the offgas recombiner where hydrogen and oxygen are catalytically recombined to form water. After recombination, the offgas is routed to a condenser to remove moisture then routed to effluent conditioning components and then to charcoal adsorber tanks. The charcoal adsorber tanks provide a delay period for radioisotope decay as the offgas mixture passes through. The mixture exiting the adsorber tanks is routed to a chimney for release to the environment.

The OGS includes sample capability from various points for radiochemistry information and system health information.

9.0 PLANT LAYOUT AND ARRANGEMENT

An innovative design-to-cost solution developed for the BWRX 300 improves the construction cost and schedule and improves safety performance during the operational and decommissioning life of the plant. The RPV, SCCV, and SC SSCs are in the below-grade portions of the RB. The RB is a vertical right cylinder shaft that mitigates the effects of external events including aircraft impact, adverse weather, flooding, fires, and earthquakes. Fuel handling equipment and pools for passive SC cooling systems are in the above-grade portion of the RB directly supported by the below-grade vertical shaft. Advanced construction methods are used for the RB to reduce construction cost and schedule by reducing the amount of excavation, concrete, and the need for backfill materials.

The RB is the only Seismic Category 1 structure in the BWRX-300 design. The below-grade cylindrical shaft for the RB design and construction method is unique compared to existing NPPs. The SCCV and RPV are situated at or below grade within the RB. A pool rests above the SCCV and interfaces with the SCCV dome. The three ICS pools sit next to the pool above the SCCV with one IC located in each pool (see Figure 9-1, *Reactor Building Showing ICS Pools*). The fuel pool is located at grade in the RB and has a capacity of eight years of used fuel and a full core off-load.

The CB, TB, and RWB structures are designed to prevent structural incident or interaction that could:

- Degrade the functioning of the RB SC1 SSCs to an unacceptable level of safety.
- Result in incapacitating injury to occupants of the CB control room.
- Compromise the safety functions of those SSCs that are required to remain functional following a seismic event.

The preliminary site secure or Protected Area (PA) layout for BWRX-300 (see Figure 9-2, BWRX-300 Site Layout) includes the security building, roadways around the power block, generator step up transformer, auxiliary transformer for site power, fencing, and general laydown areas.

The owner's area includes other plant buildings, switchyard, cooling tower (if needed), site office, parking lot, warehouse, and other supporting facilities. The reference site uses mechanical draft cooling towers, but other options are available including hybrid or dry cooling towers or once-through cooling to a lake, river, or ocean. This area can vary greatly from site to site.

The CB, TB, and RWB structures are supported by a near-surface basemat foundation adjacent to the deeply embedded RB structure. The CB, TB, and RWB are separated from the RB by seismic gaps. The CB houses the control room, electrical, control, and instrumentation equipment. The RWB houses rooms and equipment for handling, processing, and packaging liquid and solid radioactive wastes. The TB encloses the turbine generator, main condenser, CFSs, condensate purification system, OGS, turbine generator support systems, and bridge crane.

The power block is comprised of the RB, TB, CB, RWB, and the Turbine Maintenance Building.




Figure 9-1: Reactor Building Showing ICS Pools




Figure 9-2: BWRX-300 Site Layout




Figure 9-3: BWRX-300 Site Arrangement

10.0 SAFETY STRATEGY EVALUATION AND ANALYSES

10.1 Introduction

The BWRX-300 safety strategy framework integrates the DLs provided by the implementation of the D-in-D concept with the safety analyses. Section 1.2, *Safety Concept and Defense-in-Depth* defines the safety strategy framework implementation process shown in Figure 10-2, Safety Strategy Evaluation and Analyses Framework. The D-in-D concept uses insights gained from operating experience, deterministic analyses, and risk-informed and performance-based (RIPB) analyses.

Defensive layering in the design is predicated on the types of events to be protected against, their frequency of occurrence, and their potential consequences, as are the safety analyses used to confirm adequacy of the defensive layers. The BWRX-300 Safety Strategy, D-in-D, and the application of DLs, need to be understood in the context of the following concepts:

- Hazard: A hazard is defined as anything that has the potential to challenge the credited functions of plant SSCs or actions of plant personnel. For example, radiation, extreme cold, impact from heavy objects with dynamic or potential energy, floods, seismic activity, and fire are all hazards.
- 2. Incident: An incident is the loss or degradation of the properties or functions of an SSC (e.g., 'functional incident'). Incidences also include the incidence of a human to take the correct action or inadvertently take an incorrect action (i.e., "human incident event"). As incident in an SSC can result from any number of potential causes or "incident modes". As incident can cause any of the following:
 - Hazard that leads to a PIE
 - PIE (directly)
 - Loss of PIE mitigating function
- 3. PIE: A PIE represents any impact of a hazard or incident on plant operation which can challenge performance of an FSF. A PIE represents an unwanted change in state of plant equipment that initiates an event sequence. PIEs are identified through SSC functional and human incident analyses, and a representative set is selected using deterministic and probabilistic inputs.
- 4. Event Sequence: An event sequence consists of a PIE, assumed DL mitigation functional incidents (making the scenario more severe and less likely than the PIE alone), and the DL function successes which mitigate the PIE. The same PIE typically appears in multiple event sequences based on application of different DL successes and incidences in response to the PIE.
- 5. Plant States: Plant states include operational states (normal operation and anticipated operational occurrences) and accident conditions (design basis accidents and design extension conditions).
- 6. Event Categories: A category (AOO, DBA, or DEC) assigned to a PIE or event sequence based on the frequency with which it is expected to occur.

Plant states and event categories are established as a framework to organize the various safety analyses and application of D-in-D across the complete spectrum of possible plant conditions. Plant states and associated "event categories" are based on frequency of occurrence and can differ between regulatory regimes. The event categories adopted for the BWRX-300 Safety Strategy are consistent with those defined in IAEA SSG-2 (7). The interconnectedness between the safety strategy, plant design, and safety analysis are modeled in Figure 10-1, *Configuration of BWRX-300 Plant States*.




Figure 10-1: Configuration of BWRX-300 Plant States

Frequencies of occurrence which delineate transitions between the above event categories, which apply to PIEs themselves and to event sequences (which include additional incidences after the PIE) are as follows:

- 1. AOO frequency greater than 1E-02 per reactor-year
- DBA frequency from 1E-02 to 1E-05 per reactor-year
- 3. DEC frequency less than 1E-05 per reactor-year

The plant design envelope includes Normal Operation through DEC event categories, including the DEC severe accidents selected for consideration.

In the majority of cases, PIEs and event sequences are assigned to an event category based on frequency of occurrence. Limited exceptions to this approach are applied as follows:

- 1. Breaks in piping resulting in LOCA PIEs are analyzed as DBAs even if their frequency of occurrence falls in the range of DEC events. This is a conservative approach aligned with international and national regulatory requirements for water-cooled reactors. This analysis supports demonstration that adequate core cooling is maintained during postulated LOCAs. Consideration of dynamic effects (e.g., pipe whip, jet impingement.) associated with the postulated pipe breaks is excluded from the DBA LOCA analyses. Pipe breaks of a nature leading to dynamic effects are categorized as DECs based on the BEZ treatment and are analyzed with DEC acceptance criteria separate from the DBA LOCA PIE analysis.
- 2. PIEs initiated by digital CCF in DL3 are analyzed as DEC events even though the estimated frequency of occurrence falls in the range of DBA events. This approach is aligned with industry precedent regarding treatment of digital CCF events. The implications of treating such PIEs as DBAs includes requiring a second, SC1 protection system, for the specific purpose of protecting the plant against unwarranted actions by the first which performs the DL3 functions. This is not deemed practicable for a number of reasons. DL2 and DL4a functions are required to be diverse and independent from DL3 functions and have high reliability targets. These functions are demonstrated to mitigate DEC PIEs caused by digital CCF of DL3 functions.
- 3. Event sequences which include digital CCF in DL3 are analyzed as DEC events even though the estimated frequency of occurrence of a PIE and the CCF may fall in the range of DBA events. This approach is aligned with industry precedent regarding treatment of digital CCF events. The implications of treating such sequences as DBAs would include requiring a second, SC1 protection system as a backup to the first. This is deemed not practicable for a number of reasons. DL2 and DL4a functions are required to be diverse and independent from DL3 functions and have high reliability targets. These functions are demonstrated to mitigate DEC event sequences involving digital CCF of DL3 functions.
- 4. Event sequences comprising an AOO PIE and an assumed CCF of DL2 mitigation functions are analyzed as DBA events even if their estimated frequency of occurrence is in the DEC range. This is a conservative approach and assures a DL3 response, as needed to satisfy acceptance criteria for all AOO PIEs. It also assures conservative analysis methods and assumptions are used in the demonstration of the DL3 response.
- 5. Event sequences comprising a DBA PIE and an assumed CCF of DL2 mitigation functions are analyzed as DBA events even if their estimated frequency of occurrence is in the DEC range. This is a conservative approach and assures a DL3 response, as needed to satisfy acceptance criteria for all DBA PIEs. It also assures conservative analysis methods and assumptions are used in the demonstration of the DL3 response.

Design Basis hazards, both internal and external, are not categorized according to the frequency values associated with the above event categories. The Design Basis frequencies are hazard-specific and reflect the national/regional regulatory requirements for categorization. The regional location of the facility is also considered for external hazards.

10.2 Overview

This section outlines the multi-faceted approach to safety assessment that forms a key part of implementing the BWRX-300 Safety Strategy. The approach makes use of hazard evaluations, DSA, and PSA, in order to provide bases for a comprehensive set of design-to-analysis requirements which inform design development and modifications such that the design can be demonstrated to effectively satisfy analysis acceptance criteria and the plant safety goals. As with the overall Safety Strategy implementation process, the safety evaluations and analyses are performed iteratively as the design and licensing documentation are developed.

Figure 10-2, Safety Strategy Evaluation and Analyses Framework, illustrates this multi-faceted approach, highlighting the integration of the related analysis activities and outputs, as well as the links to and influences on licensing and design processes. These processes then implement required modifications and provide feedback to the next iteration of the evaluations and analyses.




Figure 10-2: Safety Strategy Evaluation and Analyses Framework

A fundamental concept of the BWRX-300 Safety Strategy is that an event sequence that assumes incident of DL functions capable of mitigating the sequence (i.e., a CCF incident of all functions in a DL that are credited to mitigate a given PIE) has a lower frequency of occurrence than if the DL functions were not assumed to fail. The assumed frequency of such an event sequence is the frequency of the PIE multiplied by the required significant frequency of incident of the DL mitigation functions postulated to fail. For example, an event sequence for a PIE with a frequency in the AOO range that assumes incidence of DL2 functions to mitigate the PIE has a frequency equal to the PIE frequency multiplied by the target reliability value for DL2 functions, which results in a sequence frequency in the DBA range. Accordingly, such an event sequence is evaluated as a DBA using acceptance criteria associated with DBAs. DL2 is not formally single incident proof, however, CCF of DL2 functions is used in the analyses as a bounding case for DL2 incidences.

Figure 10-3, Defense Lines and Event Categories per Analysis Type, further illustrates this concept. The length of each horizontal arrow in this figure shows how a postulated DL incident changes the frequency of the event sequence, based on target reliability values of 1E-02 incidences/demand for DL2, 1E-04 incidences/demand for DL3, and 1E-03 incidences/demand for DL4a. The length of the 'DL mitigation' arrows in this figure are an approximate representation of these reliability targets.

For example, row 1 illustrates an AOO PIE mitigated by DL2 functions in the BL-DSA. The reliability of DL2 is such that its incidence to mitigate the AOO PIE creates an event sequence in the DBA event category. A CN-DSA is then performed to demonstrate DL3 mitigation of the same PIE but assuming the DL2 incidence occurs. The reliability of DL3 is such that its incidence to mitigate the DBA event sequence creates an event sequence in the DEC event category.

Table 10-1, Application of Defense Lines in Safety Analyses, illustrates the acceptable combinations of DL mitigation functions for the range of PIEs, and event sequences stemming from those PIEs, which complete the scope of the DSA. Table 10-1 and Figure 10-3 are correlated by row number.




Figure 10-3: Defense Lines and Event Categories per Analysis Type

Table 10-1: Application of Defense Lines in Safety Analyses

			Safety	/ Analysis L	_ayers	
		(To form Event		Incidences d Progress		s/Analysis Layers)
PIE Type	Row #	BL-DSA mitigation	Incident assumed in CN-DSA →	CN-DSA mitigation	Incident assumed in EX-DSA →	EX-DSA mitigation
AOO PIEs	1	DL2 (1)	DL2 CCF and DL3 Single Incident	DL3		
AOO PIEs (2)	2				Hydraulic Scram Mechanical CCF	DL2 +DL4a
DBA PIEs which are not initiated by a CCF (3)	3	DL2	DL2 CCF and DL3 Single Incident	DL3		
	4	DL2 + DL3	DL2 CCF and DL3 Single Incident	DL3	DL3 CCF	DL2 + DL4a
	5	DL3	DL3 Single Incident	DL3	DL3 CCF	DL4a
DBA PIEs initiated by CCF in DL2 or DL4a	6	DL3 + Unaffected DL2 + DL4a functions	CCF – non- DL3 functions and DL3 Single Incident	DL3		
DEC PIEs which are not initiated by a CCF	7					Unaffected DL2 + DL3 + DL4a functions
DEC PIEs initiated by CCF in DL3	8					DL2 + DL4a
DEC Complex Sequences and Severe Accidents	9	uld be mitigated uping				DL4b + Unaffected DL2 + DL3 + DL4a functions

All AOO PIEs should be mitigated using only DL2 functions in the BL-DSA. If a DL3 function is necessary in the BL-DSA to mitigate an AOO PIE, a demonstration has to be provided that it is not practicable to implement a DL2 mitigation function, and an EX-DSA has to also be performed assuming CCF of DL3 mitigating functions.

2. When an AOO PIE is mitigated according to row number one, and both the BL-DSA and CN-DSA credit hydraulic scram functions, another event sequence is analyzed assuming CCF of the mechanical equipment providing the hydraulic motive force for scram.

3. The DL functions credited in the BL-DSA determine which row is followed to complete the demonstration of two functional DLs capable of mitigating the PIE.

NOTE: A "+" as used in the table means that the identified DLs may be used individually or in combination to mitigate the event sequence. It does not mean that the DLs are required to independently mitigate the event sequence.

NOTE: "Unaffected functions" refers to SSCs being able to continue to operate or to be actuated or operated because they are not rendered inoperable by the PIE, by a postulated incident that is part of the event sequence, or by consequential effects.

Ultimately, the set of evaluations and analyses demonstrate that the D-in-D design approach leads an overall plant design that meets specific acceptance criteria per event category. The approach described in this section is a layered, comprehensive, and systematic way to evaluate events, apply DL functions, and specify related requirements for the design in an iterative, progressive manner. This then provides high confidence that once these evaluations and analyses are finalized, the plant design can be demonstrated to meet overall safety goals and have successfully implemented the Safety Strategy.

10.3 Severe Accident Mitigation

The BWRX-300 capability to prevent severe reactor accidents from occurring and the capability to withstand a severe accident, in the extremely unlikely event that one should occur, are being evaluated with several PRAs during the ongoing design and safety analysis processes. The preliminary evaluations indicate that events resulting in damage to the reactor core are extremely unlikely, but that even if such events were to occur, passive accident mitigation features would limit the offsite dose such that the effect on the public and surrounding land would be insignificant.

In the unlikely event of a severe accident there are multiple design features that mitigate the results of any such accident. These features are detailed below:

- A core catcher is provided below the RPV for corium to spread and prevent contact with concrete as a mitigating feature following a severe accident. The core catcher is equipped with a corium shield liner manufactured of Zirconia to contain the corium and prevent MCCI. The complimentary design feature of containment flooding quenches the spread corium to maintain containment integrity and reduce the environmental release.
- Severe accident water addition piping supplies flooding water to the core catcher to quench the corium following an RPV incident. Quenching is required to prevent concrete material loss due to heat transfer through the core catcher and limit the containment gas temperature rise. The outer CIV is opened, priming the system, when containment design pressure is exceeded. Flooding is initiated when pedestal gas temperatures melt the fusible link material holding the flooding valve closed. Following valve opening, the flooding flow is driven passively by gravity into the pedestal region on top of the corium for quenching. Sufficient water is available to maintain the corium quenched for seven days, while additional water can be aligned to the IC outer pool for flooding via FLEX strategies.

• A connection external to the RB is provided to fill the Isolation condenser pools. This connection provides water to a common header with individual valves allowing filling of each of the isolation condenser pools. A connection external to the RB is supplied to fill the spent used fuel pool. A connection external to the RB is supplied to flood the containment via the severe accident water addition system. An external connection to liquid waste management system to supply water to the control rod drive system pumps to provide makeup water to the reactor pressure vessel. Also, there are FLEX connections on each preferred power buss A &B and each of the three emergency power buses for powering the battery chargers for the SC1 batteries.

- The fuel pool storage is configured for a seven-day coping time with no power required for used fuel cooling. After the seven days, the fuel pool can be filled via external FLEX connections if required due to evaporation.
- The FLEX equipment and storage building is not part of the standard design and is expected
 to be provided by the purchaser. It is expected that the purchaser is to allocate room in either
 the admin/training building or warehouse for storage of FLEX equipment. This can be provided
 by GVH as an option.

11.0 SITE CONSIDERATIONS AND GRID INTEGRATION

For construction, the site needs a deep-water pier for barging or heavy haul routes for land transportation. The largest component transported to site is the RPV, which is approximately 27.4 m long and 4 m in diameter and weighs approximately 650 metric tons with RPV, self-propelled modularized transports, rigging, and cribbing.

11.1 Site Considerations During Operation

The seismic design considers a wide variety of soil conditions (soft, medium, and hard rock). During normal operation, the reference site maximum acceptable ambient air temperature is 37.8 °C dry bulb (100 °F) / 26.1 °C (79 °F) mean coincident wet bulb. Maximum recommended inlet temperature for the main condenser/HX is 37.8 °C (100 °F). The BWRX-300 can be equipped with a wide variety of cooling options, including dry cooling towers and once-through cooling.

11.2 Grid Integration

Switchyard requirements are minimal, typical, and are met with a breaker and a half, dual high voltage bus design, and a relay house with controlled access as shown in Figure 11-1, *BWRX-300 Switchyard Interface*. The BWRX-300 plant only requires a minimum of one incoming/outputting transmission line capable of handling the 300 MWe/355 MVA plant output. This is possible since the BWRX-300 safety systems do not require AC power to function. The switchyard may be any voltage or frequency as needed to interface with the transmission system. The switchyard can be designed such that no single switchyard breaker or switchyard bus incident results in loss of transmission or loss of plant input power. It is recommended that the switchyard protection schemes are redundant with separate batteries and separate chargers. If required, the plant standby diesel generators can power the switchyard battery chargers. Finally, the various chargers, batteries, and protective relays are to be housed in a physically secure and protected enclosure if required. This equipment is considered critical digital assets by the Federal Energy Regulatory Commission in the U.S.

The BWRX-300 plant I&C have required interfaces with the switchyard breakers/protective relays; cyber security reasons restrict the interface to hardwired.




Figure 11-1: BWRX-300 Switchyard Interface

11.3 Research, Development, and Testing

The BWRX-300 research and development program is implemented as part of the project risk management and design processes. GVH may subcontract portions of the research and development scope to engineering and test vendors, national laboratories, or universities. For most SSCs, the BWRX-300 uses commercial off-the-shelf equipment and proven construction techniques, so the research and development program are focused on a small subset of the overall design.

System and component testing are an aspect of the design verification. Design verification is performed to help ensure the design complies with customer requirements, technical requirements, regulatory requirements, and codes and standards. Verification helps ensure that appropriate design methods are used, design inputs are appropriately incorporated into the design, and design output is reasonable when compared with the design input.

Design verification qualification tests demonstrate adequacy of performance under conditions that simulate the most adverse design conditions. Where the test is intended to verify only specific design features, other features of the design are verified by alternate approved verification methods.

Engineering tests that provide product performance or design basis information, or impact the design, licensing, or operation of a product, product line, or environmental qualification, are also used. The tests include requirements, acceptance criteria and results, and are performed by qualified individuals with sufficient controls (environmental, calibrated equipment qualified personnel) to demonstrate compliance to pertinent requirements, industry codes and standards, and regulatory requirements.

The test program also includes prototype qualification tests, production tests, proof tests before installation, and pre-operational tests to demonstrate satisfactory performance of the system/components of the BWRX-300.

12.0 TECHNOLOGY MATURITY/READINESS

The BWRX-300 leverages the main features of the power cycle from NPPs that have been or are in service. The BWRX-300 is the 10th generation BWR and draws heavily from previous designs. For example, it leverages natural circulation from the Dodewaard and ESBWR and utilizes key components from the ABWR.

The nuclear core uses the proven GNF2 fuel assemblies that are manufactured and sold to over 80% of the BWR fleet, and over 26,000 GNF2 fuel assemblies have been delivered worldwide

Below is a brief list of pre-established foundations which support and streamline the BWRX-300 design:

- GVH has approximately 40 BWR plants currently in service.
- GVH has over 2,300 BWR operating years of experience and lessons learned.
- GVH administers and coordinates a BWR Owners' Group, which deals with fleet-wide issues and concerns and operating experience.
- GVH has a USNRC-approved NQA-1 quality program, which is also approved internationally and meets the IAEA requirements for an overall quality program.
- GVH uses its version of the Transient Reactor Analysis Code thermal-hydraulic code to perform design basis analyses. The code was qualified through a series of tests that covered important phenomena which largely overlap BWRX-300 phenomena and have been approved by the USNRC for ESBWR safety analysis.

GVH is supported by GE Global Research, U.S. universities, and national labs for work with a goal of improving the design. None of these are needed to commercialize the technology but are expected to be leveraged to lower costs in the future.

Previous GE BWR designs have been licensed worldwide, including in the U.S., Japan, U.K., Taiwan, Switzerland, Italy, and Spain. In addition, the World Association of Nuclear Operators, and the U.S.-based Institute of Nuclear Power Operations both coordinate the sharing of nuclear reactor operating experience.

One of the design goals of the BWRX-300 is to be licensed internationally. The design has been developed using a philosophy which is based on the IAEA D-in-D guidelines. This creates a transparent and easy-to-follow foundation for plant SSC classification that can be adapted to the requirements of individual country regimes.

The BWRX-300 leverages proven designs with very little research and technology development needed. Only certain components need component-level testing. GVH is also exploring new nuclear manufacturing methods such as those using powder metallurgy and advanced design improvement methods. Features such as these are expected to be extensively tested before being incorporated into the design.

13.0 PLANT OPERATIONS AND MAINTENANCE

It is a primary objective of the BWRX-300 design to achieve a competitive LCOE by reducing the required on-site staff and operations and maintenance costs, along with capital costs. Financing costs also have a significant impact on LCOE. GVH can work with potential customers to assist in modeling a project specific LCOE.

The BWRX-300 is designed for minimal staffing while meeting all requirements for safe and reliable nuclear operations. The site staffing of approximately 150 employees for a single unit site is achievable by informing the design early on, improving operations and maintenance programs, and implementing fleet services.

Cycle length is determined by the owner/utility and can range from 12-24 months with outage lengths of approximately 10 to 15 days. This refueling outage period is intended to allow refueling of the reactor and maintenance of key mechanical equipment. Major outages, that last about 25 days, are expected every 10 years. These major outages allow major turbine inspections and any other non-routine inspections, as required.

Fleet operations, maintenance, and training options are being developed for a fleet of BWRX-300 plants. These options include the collection and analyses of plant data, improvement of work control, configuration management, plant procedures, centralized training, supply chain, refueling/maintenance teams, and engineering for maintenance and modifications. The savings potential and structure of moving to a centralized fleet operation, maintenance, and training model is to be evaluated from an LCOE standpoint, taking the entire lifecycle of the plant into account (i.e., not just capital cost).

14.0 SAFEGUARDS AND SECURITY

14.1 Safeguards

The BWRX-300 is consistent with operating BWRs with respect to safeguards on nuclear material. Fuel received on-site enters a Special Nuclear Material (SNM) Material Control and Accounting Program, which is the responsibility of the plant operator and management. As such, the features described here are typical, and the program can be tailored for the individual site.

The criteria prescribed in the Material Control and Accounting Program are applicable to SNM and various material mixtures containing SNM. The U-235 content varies depending on various reactor parameters. SNM is typically in the form of ceramic pellets encapsulated in metal fuel rods. Criteria are established for the SNM control and accounting system, including criteria for the receipt, internal control, physical inventory, and shipment. The remainder of this section provides key portions of a typical program.

Written procedures are prepared and maintained covering the SNM control and accounting system. These procedures address, as a minimum, the following topics:

- Organization and personnel responsibilities and authorities
- Designation and description of item control areas
- · Material control records and reporting
- Notification for events concerning SNM
- Receiving and shipping SNM
- Internal transfer of SNM
- Physical inventory of SNM
- SNM element and isotopic calculation method
- Characterization and identification of items as SNM or non-SNM to preclude loss of control of SNM items

Shipment procedures are established to provide for:

- Verification and recording of the serial number or unique identifier of each item containing SNM
- Recording of the quantities of SNM contained in each item
- Reporting the quantity of SNM shipped if the quantity is reportable
- Verification of compliance with regulations, including licensing, transportation, and security requirements for shipment
- Reporting the completion of each shipment to the accounting group

Care is taken to assure that SNM contained in fuel is not shipped inadvertently with shipments of non-fuel SNM waste.

Shipment of fuel assemblies, fuel components, or non-fuel SNM is documented in the material control records and the book inventory is updated for the applicable item control area. Nuclear Material Transaction Reports are completed.

Records are created and retained in accordance with SNM accountability requirements.

When a fuel assembly has been received by the utility, the SNM custodian takes over SNM accounting responsibilities of the fuel.

14.2 Physical Security

The Security Plan of BWRX-300 is withheld from public disclosure. This section provides general and partial information on physical security features which generally apply to BWRX-300 and to other new nuclear plants.

All vital equipment is in vital areas to which access is monitored and controlled. Much of the vital area is within radiological control areas, which are inaccessible during operation and typically only accessed during refueling intervals. Additionally, all vital areas are located within the PA, providing a second physical barrier and means of access control. The D-in-D concepts of redundancy and physical separation of redundant systems, as well as simple passive safety systems, further support the physical security of the plant in that multiple vital SSCs are to be compromised to realize effective radiological sabotage. All vital systems and components are housed within robust reinforced concrete structures that are accessed only through a minimal number of normally locked access points that are controlled and monitored by the site security system. Many of the components of vital systems are located below site grade, thereby reducing exposure to external threats.

Site physical protection is provided through a combination of a security organization, including armed personnel, physical barriers, controlled access to the PA, controlled access to vital areas located within the PA, and administrative policies and procedures for screening and monitoring personnel and material allowed access to the site.

14.3 Cyber Security Capabilities

GVH implements strong cyber security programs to control the product development lifecycles for all disciplines susceptible to cyber security issues, including I&C technology platforms. GVH's cyber security program is based on common industry standard frameworks, including the National Institute of Standards and Technology Framework for Improving Critical Infrastructure Cyber Security and the North American Energy Reliability Corporation Critical Infrastructure Protection plan. GVH further augments the GE Power product security program by ensuring that USNRC specific cyber security requirements are implemented for and integrated to DCIS offerings delivered to nuclear customers, such as 10 CFR 73.54, *U.S. Nuclear Regulatory Commission*, "Protection of Digital Computer and Communication Systems and Networks," Part 73.54, Chapter 1, Title 10, "Energy." (23) and its common implementation frameworks, such as Nuclear Energy Institute (NEI) 08-09, *Cyber Security Plan for Nuclear Power Reactors* (20). GVH addresses cyber security requirements under the applicable business policies and common procedures.

14.4 Resistance to Electromagnetic Pulse and Geomagnetic Disturbances

The BWRX-300 is designed to reduce the use of electrically controlled and operated components (for example, using natural circulation for cooling instead of forced pumping). Using fewer electrical components reduces its vulnerability to electromagnetic pulse and geomagnetic disturbances. The requirements for electromagnetic pulse are to be established early on, and these mitigation features are added as required during the detailed design. The appropriate design features to adequately harden the distributed control system equipment are used in accordance with industry best practices and lessons learned.

14.5 Electromagnetic Compatibility

Electromagnetic Compatibility qualification involves two elements: 1) testing to assess susceptibility of equipment to interference levels that bound the expected electromagnetic environment; and 2) testing to assess emissions of equipment to help ensure that the contribution to the electromagnetic environment does not invalidate bounding interference levels applied for susceptibility testing.

Electromagnetic Compatibility involves susceptibility testing and emissions testing. Susceptibility testing allows assessment of equipment immunity to Electromagnetic, and Radio Frequency Interference and confirmation of its surge withstand capability. Emissions testing provide assurance that equipment is compatible with the expected electromagnetic environment.

15.0 OTHER PLANT CHARACTERISTICS

15.1 Load Following

BWR core loadings are designed such that power maneuvering via control rod movement is performed within the BWR Fuel Operating Guidelines. The BWRX-300 core nuclear design can be improved for daily load following, using control rods only, while maintaining conformance with these guidelines. The BWRX-300 can maneuver from 100% and 50% power, with a ramp rate of +0.5%/minute, and return to full power with the same ramp rate, daily. The plant can reduce electric power at a faster rate by dumping steam to the condenser instead of using the main turbine/generator control valves. If dumping steam is expected to occur regularly for a particular plant, then an optional, higher capacity condenser is implemented.

15.2 Lower Waste Yields

Although the BWRX-300 is an LWR, it has lower lifetime waste yields and a lower end-of-life decommissioning volume compared to the current generation of operational reactors. This is due to the use of proven improvements from the current fleet of BWRs for both piping material (stainless steel) and modern in-use radioactive waste demineralizer resin material. In addition, the fuel cycle for this plant is efficient and the use of a 12-month cycle leads to fewer used fuel assemblies overall compared to 18 or 24-months operating cycles, which is the experience from BWRs in Europe. The focus on design-to-cost and a reduced construction schedule duration led to a construction method that yields less material for decommissioning purposes.

15.3 Ability to Integrate with Electric and Non-Electric Applications

Unlike current generation plants, the smaller size makes for more flexible operation and fits in existing electrical grid transmission systems without extensive upgrades. The BWRX-300 can also provide process heat for industrial usage and district heat from the waste heat generated from the MS turbine and other steam heat loads as required. Another application the BWRX-300 can be used for is green hydrogen generation. Utilizing the electrical output to power electrolyzers can produce green hydrogen that can be used for a variety of applications such as transportation or heat source for steel mills.

15.4 Energy Resilience

The BWRX-300 provides for energy resilience with the ability to avoid, prepare for, reduce, adapt to, and recover from anticipated and unanticipated energy disruptions. The BWRX-300 can be deployed to help ensure energy availability and resiliency is sufficient to provide mission assurance and readiness. This includes powering critical assets and other mission essential requirements.

As baseload power plants are being retired, there is an emerging need for newly constructed power sources. Environmental considerations are driving consumers to look toward clean energy options. However, renewable power sources are not as reliable as traditional power stations, and thus, are ill-suited sources of baseload power. Although natural gas power plants do release far less carbon than today's coal-heavy generation portfolio, they do, nonetheless, emit significant amounts of air pollutants. Hence, there is an opportunity for an environmentally friendly, reliable, and fast-responding power source.

Compared to certain other baseload power alternatives, the BWRX-300 presents an opportunity to reduce emissions from baseload power generation in the future; offers a more secure, resilient power source; and provides more reliable power as compared to renewable generation.

- Fuel Security: The BWRX-300 can store at least two years of new fuel on-site. Storing that
 much fuel on-site for a natural gas plant is impractical and expensive, given the massive
 gas storage facilities which are required. Natural gas deliveries can be subject to volatile
 segments and occasional shortages, especially during unusually cold winter weather. Coal
 and other fossil fuel are susceptible to excess moisture during wet periods.
- Ramp Up and Ramp Down: The BWRX-300 allows for output to ramp up from 50%-100% in 2 hours. This feature enables the BWRX-300 to ramp up quickly in the case of a grid outage and adjust power supply to be in line with changing load demands. The plant can reduce power quicker, if necessary, by dumping steam to the condenser instead of the main turbine/generator.
- Islanding: The BWRX-300 can operate connected to the grid or can be operated independently with additional transformers and electrical protection relays. If attached to a mini grid with islanding, the BWRX-300 could power a facility campus in the event of grid incident.
- Black Start: Black Start capabilities are not included in the standard BWRX-300, but the BWRX-300 can start up from a completely de-energized state without receiving energy from the grid if equipped with a 25-50 MW gas turbine and additional transformer connections. This can help an electricity grid meet system requirements in terms of voltage, frequency, and other attributes when recovering from an outage.
- Underground Construction: The BWRX-300 reactor is built using mainly underground structures. This design feature reduces the vulnerability to natural phenomena, environmental monitoring program, and other intentional destructive acts.
- Minimal Use of Electrical Components: The BWRX-300 is designed to reduce the use of electrically controlled and operated components (for example, using natural circulation for cooling instead of forced pumping). Using fewer electrical components reduces vulnerability to environmental monitoring program.

16.0 REACTOR END-OF-LIFE

The BWRX-300 is designed for a 60-year life with a possible life extension to 80 years. The reactor end-of-life decommissioning is another aspect of the BWRX-300 lifecycle where GVH has experience. GVH is currently engaged in decommissioning activities all around the world and this operating experience is to be included in the BWRX-300 design considerations.

16.1 BWRX-300 Design Life

While self-consolidating concretes are designed for a nominal 60-year life, they are expected to offer a plant life well beyond the designed lifetimes. The principal SSCs for the BWRX-300 are designed for a 60-year life. The layout of the systems within structures considers component replacements. The BWRX-300 life can be extended to 80 years depending on operations history and system health.

16.2 BWRX-300 Decommissioning

The decommissioning process of an LWR involves:

- Removing the used nuclear fuel from the reactor and placing it into on-site dry storage containers once the decay heat has dropped to the appropriate level.
- Dismantling systems or components containing radioactive products (e.g., the RPV).
- Cleaning up or dismantling contaminated materials from the facility.
- Disposing contaminated materials either on-site or shipping it to an available waste-processing, storage, or disposal facility.

Due to the focus on reduced quantities and overall SSCs simplification, the amounts of material (e.g., concrete, steel) is lower for the BWRX-300 compared to existing LWRs. Also, since the BWR is a direct cycle plant, there are fewer and smaller high contaminated pieces. The RPV has bolted internal components designed to be removed which simplifies the handling of contaminated materials.

At the time of BWRX-300 decommissioning, the current generation BWRs are all expected to have been decommissioned, and the lessons learned from those activities are being considered in the BWRX-300 design, operation, and decommissioning strategies. GVH is currently involved in decommissioning activities worldwide including RPV and internal cutup projects in Europe, the U.S., and Japan. There are no first-of-a-kind issues for the BWRX-300 that pose a risk to future decommissioning processes.

17.0 MANUFACTURING AND CONSTRUCTION


GVH expects to leverage the GE parent global knowledge and supply chain to deploy the BWRX-300 to those countries having Nuclear Cooperation Agreements in place with the U.S. government. Project specific contract terms are to be negotiated on an individual basis. The base design of the BWRX-300, and therefore the base cost estimate, is intended to cover a variety of sites. However, individual site parameters and characteristics such as seismicity, restrictions on water usage, local infrastructure, and availability of skilled labor impact the cost for a specific project.

Training programs with supporting simulators that are compliant with international and country-specific standards are to be deployed in parallel with physical plant construction. Additional training can be made available for customers new to nuclear energy.

The BWRX-300 design philosophy of "simplicity" and "designed for constructability" enables it to be constructed and commissioned within an anticipated duration of 30-36 months from the time of first safety-related concrete to ready to load fuel. For deployment in countries that are new to nuclear energy, nuclear experienced EPCs are available to team with GVH and local EPCs to implement the project. Local supply of commodities is encouraged to reduce the cost of deployment. However, overall supply chain localization depends on the capability, readiness, and aspirations of the receiving country, along with considering project cost versus localization.

The BWRX-300 leverages prior BWR technology to include the USNRC licensed ESBWR, ABWR, and the in-production GNF2 nuclear fuel. The BWRX-300 uses commercial off-the-shelf equipment to the greatest extent possible. This includes nuclear and non-nuclear components that are currently used in the BWR fleet (see Figure 17-1, *Existing Technology Use in BWRX-300 Reactor*) and BOP components that are deployed at dozens of combined-cycle steam turbine generating locations of similar size.

The BWRX-300 uses advanced construction methods and modularization to reduce construction time and cost. Many attributes of the BWRX-300 leverage the latest 3D and Four-Dimensional (4D) modeling during manufacturing and construction and are expected to utilize field data to keep the digital twin current with the physical construction.



* ABWR fleet has combined 22+ years of operating experience | ** Kernkraftwerk Mühleberg (KKM): 355 MWe BWR/4 in operation since 1972 | *** Dodewaard: 58MWe natural circulation BWR, 1969 ~ 1997

Figure 17-1: Existing Technology Use in BWRX-300 Reactor

17.1 General Plans for Construction

The approaches to plant construction have been chosen to reduce the risk of schedule and cost overruns. The BWRX-300 draws from proven construction methods outside of the nuclear construction industry such as the water and tunneling industry for validation of construction schedule and cost. The design allows for large modular components that can be consistently lifted, set, aligned, and fixed in place to shorten the construction schedule. The BWRX-300 also relies on the use of the latest computer-aided tools including a digital twin and 4D building information model for construction planning.

A construction sequence model is to be developed to support detailed construction sequencing for determination of travel routes, laydown areas, fabrication and storage facilities, and general construction site layout. This model determines the required site improvement changes.

Rock excavation to establish the trenches for circulating water piping and cooling tower basin/pump pit may be included with site improvement to utilize the earth moving equipment on-site and perform blasting, if required, while the craft count is low at site. Installation of circulating water piping begins as a section of trench is completed. This underground piping is excavated and installed early in the schedule to allow un-impeded access to the full construction footprint.

Pre-assembly and modularization of the RB underground structure begins simultaneously with the start of RB underground shaft excavation. This helps ensure the modules are available for pick and set according to schedule.

Construction of the RB shaft begins with a survey and establish the centerline of RB. If required, pressure grouting of voids and fractures is used in the rock strata around the perimeter and underlying the shaft as determined from site boring conducted during site investigation testing. A reinforced concrete ring is placed, outlining the outside diameter of the shaft for use as an equipment platform. Earthmoving equipment is established in the shaft and excavation commences. A circular, flat-bottomed hole is excavated to accommodate the reactor shaft and provide sufficient working area around the hole for excavation equipment. Rock anchors, wire mesh, and shotcrete lining are installed on the exposed rock face as required to prevent water entry and spalling of loose rock as the shaft is excavated to depth.

An alternate method is to re-establish the centerline of the RB in the excavation. A circular concrete guide ring is laid out and installed. This is used to align the slurry wall excavation. A circular slurry wall is installed down to sound rock in accordance with an engineered specification. Reinforcing steel is installed in each slurry wall panel to help ensure the completed construction retaining shaft resists lateral loading due to construction equipment along the shaft perimeter and possibly foundation loads from adjacent buildings. This may allow adjacent building foundations to be constructed in parallel path with construction of the below-grade portion of the RB and shorten the overall project schedule. Water stop is used between slurry wall panels to reduce ground water in-leakage into the shaft during excavation. The bottom of the slurry wall is "keyed" into the bedrock to strengthen the overall shaft and provide an additional barrier to ground water in-leakage.

Soil material is removed using conventional earth moving equipment such as tracked hoes to excavate the shaft enclosed by the slurry wall. The bedrock portion of the shaft is excavated using pavement breakers, drill and blast, or a combination of the two depending on the rock structure. All spoils and rock tailings are removed from the shaft via skip pan and crane. Once on the ground surface, the spoils from excavation are transported to the designated on-site spoils pile.

Dewatering systems are employed during shaft excavation. Areas of notable water entry are sealed via an engineered pressure grouting process, or by installing wire mesh reinforcement in combination with a shotcrete concrete layer on the wall face.

Completion of shaft excavation is followed by inspection of rock geology in the shaft walls and bottom, and noted issues are repaired per Engineering disposition. Then there is placement of a construction mud mat, waterproofing membrane, and protective concrete mat. The modular steel-concrete composite reactor base mat is set in place and joined, and the concrete mat is placed.

Modular wall and floor modules are sequentially set and joined, and concrete is placed as the RB shaft is constructed from the bottom up to grade. Major pieces of equipment, piping, and electrical gear are top-loaded and positioned as the floors are placed. Alternately, the structural modules are configured to allow this equipment to be installed later to prevent late material delivery from impacting RB shaft construction progress.

Piling installation and the subsequent excavation for the steam turbine foundation starts once the RB shaft construction has stabilized soil conditions to support perimeter loading. Steam turbine base mat, pedestals, and tabletop construction follow the completion of pile installation. The turbine pedestal and tabletop are modularized via steel-concrete composite methods to the degree economical to reduce the possibility of steam turbine work activities becoming critical path on the schedule. Radwaste and CB foundations begin when the RB shaft is brought to grade. These structures are constructed simultaneously with the TB. Early construction site crane placement is shown in Figure 17-2, *BWRX-300 Construction Site*. BOP facilities are constructed to support startup and commissioning of the plant.



Figure 17-2: BWRX-300 Construction Site

17.2 Improved Construction Approaches

A standardized construction plan that requires minor modifications to estimate and plan is the overall goal for a SMR design and construction. The key excavation feature is the reactor shaft development. Straight line shaft excavation reduces material removal and backfill requirements. Techniques used by tunneling and hydraulic industries allow the use of proven methods to accomplish this type of excavation. Initial preparation uses a diaphragm wall technique to stabilize soft side walls and allow vertical excavation down to a hard rock layer. Once the diaphragm wall is in place, standard excavating techniques are used for internal soil removal. Rock excavation allows vertical wall material removal with the possibility of rock anchor stabilization. A shotcrete liner is likely required to help stabilize and seal the rock surface. With excavation completed, the bottom of the hole is sealed with a seal plug that doubles as an initial working surface to begin the structural build.

Based on lessons learned from the AP1000 units, Diaphragm Plate Steel-Plate Composite (DP-SC) modules are being utilized for the basemat, walls, floors, and roof of the RB. DP-SC provide modularity and off critical path construction capability. DP-SC modules also eliminate the basemat to wall interface challenges experienced with the AP1000 units.

Before concrete casting, the diaphragm plates and steel faceplates provide stiffness and strength to the empty steel modules. When compared to conventional Steel-Plate Composite designs, DP-SC modules can have greater stiffness and stability in the empty module configuration due to the continuous support provided by the diaphragm plates to the steel faceplates. After concrete casting, the diaphragm plates provide structural integrity to the composite section by preventing delamination of the concrete core. Additionally, the diaphragm plates provide composite action between the steel faceplates and the concrete infill, and out-of-plane shear reinforcement for the composite section. Additional ties or shear stud anchors may be used to anchor the steel faceplates to the concrete infill and control faceplate local buckling.

DP-SC panels are fabricated in factories in sizes that that can be shipped to the construction site via truck, rail or barge depending on the location of the site. The panels are then assembled into modules at site before being lifted into final position. This approach reduces the higher cost of final in-place assembly and inspection with lower cost and off critical path assembly in both on-site fabrication areas and shop fabrication.

A multi-layered water proofing philosophy is undertaken to help ensure leak tightness. A waterproof membrane is installed between the shaft wall and the DP-SC outer plate for a first protective layer. A grouting or concrete medium is then placed between the membrane and the steel liner. The DP-SC outer plate provides an additional layer of sealing.

These modularization techniques shift cost and schedule risk off critical path. With this type of process available on-site, it is expected to generate further benefit on smaller, less critical assemblies due to availability of facilities which further improve the construction process.

17.2.1 Area-by-Area Modularization of Systems, Structures, and Components

The BWRX-300 modularization program has developed its approach and methodologies based on a study of four modular component categories (illustrated in Figure 17-3, *BWRX-300 Modular Systems, Structures, and Components*):

- 1. Reactor Building (RB) Structure
- Major Components Large modular items including Reactor Pressure Vessel (RPV), Containment Equipment and Piping Support System (CEPSS), turbine, and generator
- 3. Mechanical, Electrical, Instrumentation, Control, and Automation (MEICA) Modules (within both RB and conventional island
- Conventional Island Building Structure (including precast concrete, steel and premanufactured reinforcement)

These categories are applied to every design area using a graded approach to improve initial cost and schedule savings. The initial configuration is to iterate based on ongoing improvement analysis.

Each plant area is evaluated for optimal modularization, considering factors like safety improvements, transportability and lifting constraints, supply chain capability, costs, cost savings, schedule improvements, equipment density and design risk. Most plant spaces are expected to benefit from high modularity. Each area is qualitatively evaluated by a team across functions like construction, transportation, suppliers, operations, maintenance, design and licensing for a conceptual modular solution. Each area's conceptual solution undergoes a cost- benefit analysis, weighing modularization benefits against additional costs and design risk. These analyses guide adjustments to the solution or inform modularization tier grouping.

A layered approach to shaft structure assembly also improves the opportunity to perform "Open-Top" assembly of components and piping. Setting pipe and equipment in place can be a time intensive operation. By setting equipment modules and pipe spools into place prior to setting the next level, a time savings can be realized. Design of the RB structure still allows the placement of all equipment in a non "Open-Top" which provide schedule flexibility and simplifies future maintenance (see Figure 17-4, Reactor Building DP-SC Installation Sequence). This allows schedule control to remain with the Engineering, Procurement, and Construction (EPC) contractor and removes potential issues caused by manufacturing delays.




Figure 17-3: BWRX-300 Modular Systems, Structures, and Components




Figure 17-4: Reactor Building Diaphragm Plate Steel-Plate Composite Installation Sequence

17.3 Approaches to Component Manufacture

Many of the components utilized in the BWRX-300 have significant experience in the nuclear and power industries along with an existing supply chain, which reduces risk and cost uncertainty. The risks reduced include removal of uncertainty in the manufacturing, material behavior, testing, Quality Assurance (QA), and acceptance by the USNRC and various codes. Novel approaches such as electron beam welding and powder metallurgy hot isostatic pressing are expected to be utilized for the BWRX-300 once they are proven and accepted by regulators.

The BWRX-300 is expected to employ factory assembly of the turbine and generator, which has proven to be cost-effective in the combined-cycle industry. This approach eliminates the need for open-top or open-ended assembly of tolerance critical equipment in a construction environment, reduces the risk of foreign particle entry, and reduces exposure of the internal components to elements. Assembling this equipment in a shop environment by craftsmen that perform these tasks on manufacturer specific equipment daily improves quality.




Figure 17-5: Reactor Building Structure

The reactor internals are modularized into the RPV before shipping. The entire RPV module is planned for installation in a single lift through the reactor cavity pool opening, and the CEPSS modules, as shown below in Figure 17-6, RPV Installation.




Figure 17-6: Reactor Pressure Vessel Installation

Incorporating 55% of the reactor internals into the RPV before installation moves additional person hours off-site, further streamlining the RPV installation. This shifts the critical path from the RPV to the RB structure, shown to the left in Figure 17-5, *Reactor Building Structure*, reducing the overall project duration.

Oak Ridge National Laboratory is leading an effort to determine if additive manufacturing can improve the cost and schedule for the swirling vanes in the steam separators and the header/tube assembly in the ICs. The end goal is to develop an automated process to rapidly manufacture the components with specific surface finish at a high level of quality, short schedule, and low cost.

17.4 Procurement Plans

17.4.1 Engineering, Procurement, and Construction Procurement

Part of the BWRX-300 design-to-cost target is to focus on reducing equipment which requires a specialized manufacturer to potentially be outside the EPC's normal supply chains. This allows the EPC to improve the use of established supply chains that contain vendors the EPC has previously vetted for performance and quality.

The BWRX-300 desires to leverage integration of an experienced EPC vendor using established, proven materials and control programs, for the purchase of SC and SCN commodity items, such as cable, tubing, and concrete. Historically, nuclear projects have far more safety-related components than the BWRX-300 and typically procure most commodity items to the higher, safety-related pedigree to prevent inadvertent application of a commodity. The materials control program lowers procurement costs and shortens lead time. Procurement of SC1 and ASME commodities can be made early for potential long lead items, but SC2, SC3, and SCN commodities are readily available and can be procured closer to a just-in-time method to reduce storage costs and initial capital outlay.

EPC procurement professionals provide expertise in all aspects of a procurement management program, including sourcing, purchasing, subcontracting, expediting, shop inspection, logistics, diversity management, change management, invoice administration, material management, and warranty. The EPC vendor maintains an emphasis on the fundamentals of safety, quality, schedule, cost, performance, and documentation.

Use of the EPC vendor's existing supply chains is key because it enables the EPC vendor to rely on its prequalified suppliers instead of expending resources to qualify new vendors under the EPC vendor's QA program.

The EPC vendor's contract management coordinates key equipment inspections and supplier surveillance, mitigates schedule impacts through early intervention, provides shipping logistics to support equipment and material arrival and storage on-site, and manages the overall warranty program.

17.4.2 GVH Supply Chain

The overall supply chain strategy for procuring equipment, material, and services for new nuclear plants follows these basic steps:

- 1. Understanding of customer requirements for procurement of equipment, components, and materials (e.g., "Improve Localization", supplier indigenous participation targets, cost)
- 2. Alignment of GVH business requirements with customer requirements
- 3. Performance of initial supplier search:
 - Existing and proven GVH supply chain (currently in use by GVH Services)
 - Proven nuclear suppliers with an already established relationship with GVH (e.g., used in past projects to fabricate ABWR and BWR components)
 - Other existing commercial nuclear suppliers currently providing components to the existing Global fleet
- 4. Screening of suppliers to help meet project requirements
- 5. Supplier assessment site visit
- 6. Finalization of suppliers to receive request for quotation
- 7. Request for quotation sent to and received from suppliers
- 8. Review of supplier proposals and negotiate, as required
- 9. QA audit to approve the supplier, if required
- 10. Final selection of supplier
- 11. Finalization of contractual documents (e.g., Supply Agreement, Purchase Order)

- 12. Placement of purchase order
- 13. Supplier management and oversight

GVH has a proven supply chain for critical equipment and components. Lead times for these components have been incorporated into the overall project schedule. GVH continues to help ensure that specific customer requirements are identified and incorporated into the procurement process.

18.0 ACRONYMS, DEFINITIONS, AND SYMBOLS

18.1 Acronyms

Acronym	Explanation
3D	Three-Dimensional
4D	Four-Dimensional
ABWR	Advanced Boiling Water Reactor
AC	Alternating Current
AHU	Air Handling Unit
AOO	Anticipated Operational Occurrence
ASME	American Society of Mechanical Engineers
BDBA	Beyond Design Basis Accident
BIS	Boron Injection System
ВОР	Balance of Plant
BPVC	Boiler and Pressure Vessel Code
BWR	Boiling Water Reactor
СВ	Control Building
CCF	Common Cause Failure
CCS	Containment Cooling System
CEPSS	Containment Equipment and Piping Support System
CFD	Condensate Filters and Demineralizers System
CFR	Code of Federal Regulations
CFS	Condensate and Feedwater Heating System
CIV	Containment Isolation Valve
CNSC	Canadian Nuclear Safety Commission
CRD	Control Rod Drive
CRDH	Control Rod Drive Hydraulic
CST	Condensate Storage Tank
CWE	Chilled Water Equipment
CWS	Circulating Water System
D-in-D	Defense-in-Depth
DBA	Design Basis Accident
DC	Direct Current
DCIS	Distributed Control and Information System
DEC	Design Extension Condition
DL	Defense Line

Acronym	Explanation
DP-SC	Diaphragm Plate Steel-Plate Composite
EDS	Electrical Distribution System
EPC	Engineering, Procurement, and Construction
ESBWR	Economic Simplified Boiling Water Reactor
FMCRD	Fine Motion Control Rod Drive
FPC	Fuel Pool Cooling and Cleanup System
FSF	Fundamental Safety Function
FW	Feedwater
GE	General Electric
GVH	GE Hitachi Nuclear Energy
GT	Gamma Thermometer
HCU	Hydraulic Control Unit
HFE	Human Factors Engineering
HP	High Pressure
HSI	Human-System Interface
HX	Heat Exchanger
I&C	Instrumentation and Control
IAEA	International Atomic Energy Agency
IC	Isolation Condenser
ICC	ICS Pool Cooling and Cleanup System
ICS	Isolation Condenser System
INSAG	International Nuclear Safety Group
LCOE	Levelized Cost of Electricity
LOCA	Loss-of-Coolant Accident
LOOP	Loss-of-Offsite Power
LP	Low Pressure
LPRM	Local Power Range Monitor
LTR	Licensing Topical Report
LWM	Liquid Waste Management System
LWR	Light Water Reactor
MCA	Main Condenser and Auxiliaries
MCCI	Molten Core Concrete Interaction
MCR	Main Control Room
MIT	Massachusetts Institute of Technology
MS	Main Steam

Acronym	Explanation
MSCIV	Main Steam Containment Isolation Valve
MSL	Main Steam Line
MSR	Moisture Separator Reheater System
MSRIV	Main Steam Reactor Isolation Valve
MTU	Metric Ton of Uranium
MVA	Megavolt Ampere
NBS	Nuclear Boiler System
NEI	Nuclear Energy Institute
NHS	Normal Heat Sink
NSSS	Nuclear Steam Supply System
OGS	Offgas System
PA	Protected Area
PAA	National Atomic Energy Agency (Poland)
PCCS	Passive Containment Cooling System
PCS	Primary Containment System
PIE	Postulated Initiating Event
QA	Quality Assurance
RB	Reactor Building
RCCWS	Reactor Component Cooling Water Subsystem
RCPB	Reactor Coolant Pressure Boundary
RHX	Regenerative Heat Exchanger
RIV	Reactor Isolation Valve
RPV	Reactor Pressure Vessel
SBWR	Simplified Boiling Water Reactor
SC	Safety Class
SCCV	Steel-Plate Composite Containment Vessel
SCN	Non-Safety Class
SCR	Secondary Control Room
SDC	Shutdown Cooling System
SJAE	Steam Jet Air Ejector
SMR	Small Modular Reactor
SNM	Special Nuclear Material
SRV	Safety Relief Valve
SSCs	Structures, Systems, and Components
SÚJB	State Office for Nuclear Safety (Czech Republic)

Acronym	Explanation
SURAO	Radioactive Waste Repository Authority (Czech Republic)
SWM	Solid Waste Management System
ТВ	Turbine Building
TCCWS	Turbine Component Cooling Water Subsystem
TLOS	Turbine Lube Oil System
TMR	Triple Modular Redundant
TS	Technical Specification
TSV	Turbine Stop Valve
U.K.	United Kingdom
U.S.	United States
USNRC	U.S. Nuclear Regulatory Commission
WRNM	Wide Range Neutron Monitor

18.2 Definitions

18.2.1 BWRX-300 Main Parts List Descriptions

MPL	Description
A	Plant General Information and Requirements
A11	Plant General Requirements Documents
A12	Plant Arrangement and 3D Model
A13	Architectural Design
A14	Site Works, Construction and Excavation
A15	Technical Decisions and Evaluations
A16	Technical Specifications
A17	Probabilistic Safety Assessment
A18	Reliability Availability and Maintainability Documents
A21	Deterministic Safety Analyses
A22	Application Engineering Information
A23	Radiation Environment and Shielding Design
A25	Seismic and Dynamic Loads
A31	Human Factors Engineering
A32	Instrumentation and Control Engineering
A33	Electrical Engineering
A34	Mechanical Engineering
A40	Structural and Civil Design
A50	Composite Engineering

A51	Modularization
A60	General Procurement Documents
A70	General Quality Assurance and Testing Documents
A72	Field Testing and Inspection Documents
A75	Training Documents
A80	General Operation and Maintenance Documents
A90	Certification and Licensing Documents
A93	Simulator Documents
В	Nuclear Steam Supply Systems
B21	Nuclear Boiler System
С	Control and Instrumentation Systems
C10	Primary Protection System
C11	Diverse IC Isolation System
C20	Diverse Protection System
C21	Gamma Thermometer Data Acquisition System
C22	FMCRD Motor Control System
C30	Anticipatory Protection System
C31	Reactor Control System
C32	Reactor Auxiliaries Control System
C33	Equipment Cooling and Environmental Control System
C34	Electrical Power Supply Control System
C35	Reactivity Monitoring System
C36	Plant Data Acquisition, Data Communications, and Normal Operator Interface System
C37	Control and Monitoring System for DL4B Functions
C38	Turbine Generator Control System
C39	Normal Heat Sink and Condensate/FW Control System
C40	Investment Protection System
C41	Plant Performance Monitoring
C42	Plant Environmental Monitoring Interfaces
C43	Water Chemistry
C44	Effluent Cleanup Control System
C45	Network Communications and Operator Interface System

D	Radiation Monitoring Systems
D11	Process Radiation and Environmental Monitoring System
_	One On alling Overtone
E	Core Cooling Systems
E52	Isolation Condenser System
F	Reactor Servicing Equipment
F15	Refueling and Servicing Equipment System
G	Auxiliary Systems
G11	Boron Injection System
G12	Control Rod Drive System
G20	Isolation Condenser Pools Cooling and Cleanup System
G22	Shutdown Cooling System
G31	Reactor Water Cleanup System
G41	Fuel Pool Cooling and Cleanup System
Н	Control Panels, Cabinets, and Platforms
H10	SC1 Primary Protection Platform
H11	SC1 Diverse Protection Platform
H20	SC2 Diverse Protection Platform
H21	Gamma Thermometer Data Acquisition Platform
H22	FMCRD Motor Control Platform
H23	Emergency Rod Insertion Panels Platform
H24	SC2 Video Display Platform
H30	SC3 Primary DCIS Platform
H31	SC3 Industrial PC Platform
H32	Turbine Control System Platform
H33	Rod Control and Information System Platform
H34	SC3 Video Display Platform
H35	Core Monitoring Platform
H40	SCN Primary DCIS Platform
H41	Condition Monitoring Platform
H42	Cyber Security Intrusion Detection and Monitoring Platform
H91	Control Rooms
H92	Emergency and Outage Support Facilities

H93 Simulator H94 Computer-Based Procedure System J **Nuclear Fuel** J11 Core and Fuel K Radwaste Systems K10 Liquid Waste Management System K20 Solid Waste Management System K30 Offgas System Ν **Power Cycle Systems** N21 Condensate and Feedwater Heating System N25 Condensate Filters and Demineralizers System N31 Main Turbine Equipment N35 Moisture Separator Reheater System N37 **Turbine Bypass System** N41 Generator and Exciter N61 Main Condenser and Auxiliaries N71 Circulating Water System Ρ **Station Auxiliary Systems** P25 Chilled Water Equipment P40 Plant Cooling Water System P52 Plant Pneumatics System P73 Hydrogen Water Chemistry System P85 Zinc Injection Passivation System P87 On-Line Noblechem™ System R **Electrical Distribution Systems** Emergency Power Backup DC and UPS Electrical System R10 R15 Lighting and Service Power System R20 Standby Power System R30 Preferred Power System R31 Cable and Raceway System R41 Grounding and Lightning Protection System

R51	Non-DCIS Communication System
R61	Freeze and Cathodic Protection System
S	Power Transmission Systems
S21	Switchyard
т	Containment and Environmental Control Systems
T10	Primary Containment System
T31	Containment Inerting System
T41	Containment Cooling System
U	Structures and Servicing Systems
U31	Cranes, Hoists and Elevators
U41	Heating Ventilation and Cooling System
U43	Fire Protection System
U50	Equipment and Floor Drain System
U71	Reactor Building Structure
U72	Turbine Building Structure
U73	Control Building Structure
U74	Radwaste Structure
U87	Pumphouse Structure
W	Intake Structure and Servicing Equipment
W24	Normal Heat Sink
Y	Yard Structures and Equipment
Y53	Water, Gas, and Chemical Pads
Y86	Security
Y99	Yard/BOP

18.3 Symbols

Symbol	Definition
°C	degree Celsius
°F	degree Fahrenheit
g	gram
GWd	Gigawatt-day
h	hour
Hz	hertz
kg	kilogram
km	kilometer
kW	kilowatt
m	meter
mm	millimeter
MPa	megapascal
MW	megawatt
MWe	megawatts electric
MWth	megawatts thermal
S	second
yr	year

19.0 REFERENCES

1. 006N3441, *BWRX-300 Applicable Codes, Standards, and Regulations List*, GE Vernova Hitachi Nuclear Energy Americas LLC.

- 2. 26A6642AD, ESBWR Design Control Document, Tier 2 Chapter 1: Introduction and General Description of Plant Sections 1.1 1.11, GE Vernova Hitachi Nuclear Energy Americas LLC.
- 3. Aas, D. et al., *Pacific Northwest Zero Emitting Resources Study, Energy & Environmental Economics*, 2020. https://www.energy-northwest.com/Documents/E3%20Study%20Executive%20Summary%20final.pdf
- 4. Buongiorno, J. et al., co-chair, *The Future of Nuclear Energy in a Carbon-Constrained World*: *An Interdisciplinary MIT Study*, Massachusetts Institute of Technology, 2018. http://energy.mit.edu/research/future-nuclear-energy-carbon-constrained-world/
- 5. Economic Drivers, Barriers, and Impacts in the United States, Electric Power Research Institute, 2018.
- 6. EPRI 3002011803, Exploring the Role of Advanced Nuclear in Future Energy Markets.
- 7. General Electric, *Air-Cooled Generator (GEN-A)*, (April 14, 2023. https://www.ge.com/power/gas/generators/air-cooled-topair
- 8. General Electric, *GNF2 Fuel Assembly*, (April 14, 2023). https://nuclear.gepower.com/fuel-a-plant/products/gnf2-advantage
- 9. General Electric. (April 14, 2023). *Steam Turbines for Fossil, Nuclear, and Renewable Applications*. https://www.ge.com/power/steam/steam-turbines
- 10. IAEA SF-1, *Fundamental Safety Principals*, International Atomic Energy Agency, Vienna, 2006.
- 11. IAEA SSG-2, Rev.1, *Deterministic Safety Analysis for Nuclear Power Plants*, International Atomic Energy Agency, Vienna, 2019.
- 12. IAEA SSG-30, Safety Classification of Structures, Systems and Components in Nuclear Power Plants, International Atomic Energy Agency, Vienna, 2014.
- 13. IAEA SSG-53, Design of the Reactor Containment and Associated Systems for Nuclear Power Plants, International Atomic Energy Agency, Vienna, 2019.
- 14. IAEA SSG-61, Format and Content of the Safety Analysis Report for Nuclear Power Plants, International Atomic Energy Agency, Vienna, 2021.
- 15. IAEA SSR-2/1, Safety of Nuclear Power Plants: Design, International Atomic Energy Agency, 2016.
- 16. IAEA Status Report 98, *Advanced Boiling Water Reactor II (ABWR II)*, International Atomic Energy Agency, July 2011. https://aris.iaea.org/PDF/ABWR-II.pdf
- 17. IAEA Status Report 100, *Economic Simplified Boiling Water Reactor*, International Atomic Energy Agency, July 2011. https://aris.iaea.org/PDF/ESBWR.pdf
- 18. IEA, *Nuclear Power in a Clean Energy System*, International Energy Agency, May 2019. https://www.iea.org/reports/nuclear-power-in-a-clean-energy-system
- 19. INSAG-10, *Defense in Depth in Nuclear Safety*, International Atomic Energy Agency, Vienna, 1996.

20. NEI 08-09, Rev. 6, *Cyber Security Plan for Nuclear Power Reactors*, Nuclear Energy Institute, April 2010.

- 21. REGDOC-2.5.2, *Design of Reactor Facilities: Nuclear Power Plants*, Canadian Nuclear Safety Commission, May 2014.
- 22. U.S. Code of Federal Regulations, "Standards for Protection Against Radiation," Part 20, Chapter 1, Title 10, "Energy".
- 23. U.S. Code of Federal Regulations, "Domestic Licensing of Production and Utilization Facilities," Part 50, Chapter 1, Title 10, "Energy," Appendix I, "Numerical Guides for Design Objectives and Limiting Conditions for Operation to Meet the Criterion "As Low As Reasonably Achievable" for Radioactive Material in Light-Water-Cooled Nuclear Power Reactor Effluents".
- 24. U.S. Code of Federal Regulations, "Definitions," Part 50.2, Chapter 1, Title 10, "Energy".
- 25. U.S. Nuclear Regulatory Commission, "Protection of Digital Computer and Communication Systems and Networks," Part 73.54, Chapter 1, Title 10, "Energy." Energy and Environmental Economics, Inc. (January 29, 2020).

20.0 APPENDIX A – BWRX-300 PARAMETERS OF INTEREST

Table 20-1: BWRX-300 General Parameters of Interest

Parameter Description	Value	Comments
Current/Intended Purpose	Commercial – Electric	
Main Intended Application (once commercial)	Baseload with load following capabilities	
Reference Location	Below-Ground	
Reference Site Design (reactor units per site)	Single Unit	
Reactor Core Size (1 core)	Small	Small (<1000 MWth)
Reactor Type	BWR	
Core Coolant	H ₂ O	
Neutron Moderator	H ₂ O	
NSSS Layout	Direct cycle	
Primary Circulation	Natural	
Thermodynamic Cycle	Rankine	
Secondary Side Fluid	n/a	Direct cycle, no secondary side
Fuel Form	Fuel Assembly/Bundle	
Fuel Lattice Shape	Square	
Rods/Pins per Fuel Assembly/Bundle	92	
Fuel Material Type	UO ₂	
Design Status	Preliminary	
Licensing Status	Licensing and Pre-licensing Initiated	Licensing is underway in Canada, US, Poland and U.K.

Table 20-2: BWRX-300 Parameters of Interest

Parameter Description	Value	Units or Examples
	Plant Infrastructure	
Design Life	60	Years
Lifetime Capacity Factor	95 (target)	%, defined as Lifetime MWe-yrs delivered / (MWe capacity * Design Life), incl. outages
Major Planned Outages	10-15 days every 12-24 months (refueling) 25 days every 120 months (major turbine inspection and in-service inspection on reactor vessel and internals)	# days every # months (specify purpose, including refueling)
Operation/Maintenance Human Resources	~150 total	# Staff in Operation / Maintenance Crew during Normal Operation for a single unit
Reference Site Design	1	# Units/Modules
Capacity to Electric Grid	~300	MWe (net to grid)
Non-electric Capacity	Flexible	
In-House Plant Consumption	10-30	MWe
Plant Footprint	9,800	m² (rectangular building envelope)
Site Footprint	27,100	m² (fenced area)
Emergency Planning Zone	0.35 (At site boundary)	km (radius)
Load Following Range and Speed	50 – 100% daily, 0.5% per minute	
Seismic Design (SSE)	0.3	g (Safe Shutdown Earthquake)
NSSS Operating Pressure	7.17	MPa(abs)
Primary Coolant Inventory (incl. pressurizer)	1,820,000	kg
Nominal Coolant Flow Rate	1827	kg/s
Core Inlet / Outlet Coolant Temperature	270/288	°C / °C
Available Temperature as Process Heat Source	Flexible 100-260	°C
NSSS Largest Component	RPV	
dimensions	27.4 / 4 / 650,000 (includes self-propelled modularized transports, rigging, and cribbing)	m (length) / m (diameter) / kg (transport weight)

Table 20-2: BWRX-300 Parameters of Interest

Parameter Description	Value	Units or Examples
Reactor Vessel Material	SA508	
Containment Type and Total Volume	Dry (single, underground) / 12,000	Type / m³
Rated Containment Pressure	4.14/60	bar/PSI
Spent Fuel Pool Capacity and Total Volume	8 / ~1,300	Years of full power operation / m ³
	Fuel/Core	
Single Core Thermal Power	870	MWth
Refueling Cycle	12-24	Months
Fuel Material	UO ₂	
Enrichment (avg./max.)	3.81/ 4.95	%
Fuel Cladding Material	Zircaloy-2	
Number of Fuel "Units"	240	Assemblies
Total Fissile Loading (initial)	~ 44,760 kg of U	kg fissile material
Core Discharge Burnup	~50	GWd/MTU
Reprocessing	None	
Main Reactivity Control	Rods	
Solid Burnable Absorber	B ₄ C, Hf, Gd ₂ O ₃	
Core Volume (active)	22	m³ (used to calculate power density)
	Safety Systems	
Reactor shutdown	3	Three trains with diverse backup systems that control hydraulic scram in Defense Line 3. Electric run-in of control rods in Defense Line 4a
Core injection	2	100% (HP injection through CRD system) / (no core injection required for LOCA mitigation)
Decay heat removal	2	Two 100% trains
Emergency Core Cooling	3	Three 100% ICS trains
Containment Isolation	3	Three trains with diverse backup systems
Containment cooling	2	Two 100% trains
Passive Containment	3	Three passive trains – always in service

Table 20-2: BWRX-300 Parameters of Interest

Parameter Description	Value	Units or Examples				
Emergency AC supply (e.g., diesels)	0	Two non-emergency diesels for plant investment protection. The diesels are not required for reactor safety				
DC Power Capacity (e.g., batteries)	72	Hours				
Events in which <i>Immediate Operator Action</i> is required	None					
Limiting (shortest) Subsequent Operator Action Time	24	Hours (that are assumed when following EOPs)				
Core Damage Frequency (CDF)	Estimated <1E-7	per reactor-year (based on reference site and location)				
Large Release Frequency (LRF)	Estimated <1E-8	per reactor-year (based on reference site and location)				
Overall Build Project Costs Estimate or Range (excluding Licensing, based on the Reference Design Site and Location)						
Construction Time (nth-of-a-kind)	<30	Months from first nuclear concrete to ready for fuel load				

21.0 APPENDIX B – BOILING WATER REACTOR EXPERIENCE

There have been over 100 BWRs built and operated around the world with two ABWRs currently under construction. The highest concentration of BWRs is in the U.S. where roughly one-third of the operating reactors are BWRs. Many BWRs are among the best operating plants in the world, performing in the "best of class" category. See Table 21-1, *GE Boiling Water Reactors Worldwide* for a list of GE BWRs that have been built and Table 21-2, *Non-GE Boiling Water Reactors Worldwide* for a list of Non-GE BWRs that have been built.

Table 21-1: GE Boiling Water Reactors Worldwide

Country	Plant Name	Unit No.	Model	Capacity (MW)	Begin Building	Commercial Operation
Cormony	Gundremmingen	Α	GE BWR-1	237	1962-12-12	1967-04-12
Germany	Kahl	1	GE BWR	15	1958-07-01	1962-02-01
India	Tarapur	1	GE BWR-1	150	1964-10-01	1969-10-28
iliula	Tarapur	2	GE BWR-1	150	1964-10-01	1969-10-28
Italy	Caorso	1	GE BWR-4	860	1970-01-01	1981-12-01
Italy	Garigliano	1	GE BWR-1	150	1959-11-01	1964-06-01
	Fukushima Daiichi	1	GE BWR-3	439	1967-07-25	1971-03-26
	Fukushima Daiichi	2	GE BWR-4	760	1969-06-09	1974-07-18
	Fukushima Daiichi	6	GE BWR-5	1067	1973-10-26	1979-10-24
lanan	Kashiwazaki-Kariwa	6	GE ABWR	1315	1992-11-03	1996-11-07
Japan	Kashiwazaki-Kariwa	7	GE ABWR	1315	1993-07-01	1997-07-02
	JPDR	1	GE BWR	11	1960	1962
	Tōkai	2	GE BWR-5	1060	1973-10-03	1978-11-28
	Tsuruga	1	GE BWR-2	340	1966-11-24	1970-03-14
Mexico	Laguna Verde	1	GE BWR-5	777	1976-10-01	1990-07-28
Wexico	Laguna Verde	2	GE BWR-5	775	1977-06-01	1995-04-10
Netherlands	Dodewaard	1	GE BWR-2	55	1965-05-01	1969-03-26
Spain	Cofrentes	1	GE BWR-6	1064	1975-09-09	1985-03-11
Switzerland	Leibstadt	1	GE BWR-6	1220	1974-01-01	1984-12-15
Switzeriand	Mühleberg	1	GE BWR-4	373	1967-03-01	1972-11-06
	Jinshan	1	GE BWR-4	636	1972-06-02	1978-12-10
	Jinshan	2	GE BWR-4	636	1973-12-07	1979-07-15
Taiwan	Kuosheng	1	GE BWR-6	985	1975-11-19	1981-12-28
I alwall	Kuosheng	2	GE BWR-6	985	1976-03-15	1983-03-16
	Lungmen	1	GE ABWR	1350	1999-03-31	
	Lungmen	2	GE ABWR	1350	1999-08-30	
	Big Rock Point	1	GE BWR-1	67	1960-05-01	1963-03-29
LICA	Browns Ferry	1	GE BWR-4	1200	1967-05-01	1974-08-01
USA	Browns Ferry	2	GE BWR-4	1200	1967-05-01	1975-03-01
	Browns Ferry	3	GE BWR-4	1210	1968-07-01	1977-03-01

Table 21-1: GE Boiling Water Reactors Worldwide

Country	Plant Name	Unit No.	Model	Capacity (MW)	Begin Building	Commercial Operation
	Brunswick	1	GE BWR-4	938	1970-02-07	1977-03-18
	Brunswick	2	GE BWR-4	932	1970-02-07	1975-11-03
	Clinton	1	GE BWR-6	1062	1975-10-01	1987-11-24
	Columbia	1	GE BWR-5	1131	1972-08-01	1984-12-13
	Cooper	1	GE BWR-4	769	1968-06-01	1974-07-01
	Dresden	1	GE BWR-1	197	1956-05-01	1960-07-04
	Dresden	2	GE BWR-3	894	1966-01-10	1970-06-09
	Dresden	3	GE BWR-3	879	1966-10-14	1971-11-16
	Duane Arnold	1	GE BWR-4	601	1970-05-22	1975-02-01
	Edwin I. Hatch	1	GE BWR-4	924	1968-09-30	1975-12-31
	Edwin I. Hatch	2	GE BWR-4	924	1972-02-01	1979-09-05
	Fermi	2	GE BWR-4	1115	1972-09-26	1988-01-23
	Grand Gulf	1	GE BWR-6	1401	1974-05-04	1985-07-01
	Hope Creek	1	GE BWR-4	1172	1976-03-01	1986-12-20
	Humboldt Bay	1	GE BWR-1	63	1960-11-01	1963-08-01
	James A. Fitzpatrick	1	GE BWR-4	813	1968-09-01	1975-07-28
	LaSalle County	1	GE BWR-5	1137	1973-09-10	1984-01-01
	LaSalle County	2	GE BWR-5	1140	1973-09-10	1984-10-19
	Limerick	1	GE BWR-5	1134	1974-06-19	1986-02-01
	Limerick	2	GE BWR-5	1134	1974-06-19	1990-01-08
	Millstone	1	GE BWR-3	641	1966-05-01	1970-12-28
	Monticello	1	GE BWR-3	628	1967-06-19	1971-06-30
	Nine Mile Point	1	GE BWR-2	613	1965-04-12	1969-12-01
	Nine Mile Point	2	GE BWR-5	1277	1975-08-01	1988-03-11
	Oyster Creek	1	GE BWR-2	619	1964-12-15	1969-12-23
	Peach Bottom	2	GE BWR-4	1300	1968-01-31	1974-07-05
	Peach Bottom	3	GE BWR-4	1331	1968-01-31	1974-12-23
	Perry	1	GE BWR-6	1240	1974-10-01	1987-11-18
	Pilgrim	1	GE BWR-3	677	1968-08-26	1972-12-09
	Quad Cities	1	GE BWR-4	908	1967-02-15	1973-02-18
	Quad Cities	2	GE BWR-4	911	1967-02-15	1973-03-10
	River Bend	1	GE BWR-6	967	1977-03-25	1986-06-16
	Shoreham	1	GE BWR-4	820	1972-11-01	1986-08-01
	Susquehanna	1	GE BWR-5	1257	1973-11-02	1982-11-12
	Susquehanna	2	GE BWR-5	1257	1973-11-02	1984-06-27

Table 21-1: GE Boiling Water Reactors Worldwide

	Country	Plant Name	Unit No.	Model	Capacity (MW)	Begin Building	Commercial Operation
		Vallecitos	1	GE VBWR	25	1956-01-01	1957-10-19
I		Vermont Yankee	1	GE BWR-4	605	1967-12-11	1972-11-30

Table 21-2: Non-GE Boiling Water Reactors Worldwide

Country	Plant Name	Unit No.	Model	Capacity (MW)	Begin Building	Commercial Operation
Canada	Gentilly	1	CANDU BLWR 250	250	1966-09-01	1972-05-01
Finland	Olkiluoto	1	ASEA-III, BWR-2500	890	1974-02-01	1979-10-10
Finiano	Olkiluoto	2	ASEA-III, BWR-2500	890	1975-11-01	1982-07-10
	Brunsbüttel	1	BWR-69	771	1970-04-15	1977-02-09
	Grosswelzheim	1	BWR	25	1965-01-01	1970-08-02
	Gundremmingen	В	BWR-72 (KWU)	1284	1976-07-20	1984-07-19
	Gundremmingen	С	BWR-72 (KWU)	1288	1976-07-20	1985-01-18
Germany	Isar	1	BWR-69	878	1972-05-01	1979-03-21
	Krümmel	1	BWR-69 (KWU)	1346	1974-04-05	1984-03-28
	Lingen	1	BWR	183	1964-10-01	1968-10-01
	Philippsburg	1	BWR-69	890	1970-10-01	1980-03-26
	Würgassen	1	BWR-69 (AEG)	640	1968-01-26	1975-11-11
	Fukushima Daiichi	3	Toshiba BWR-4	760	1970-12-28	1976-03-27
	Fukushima Daiichi	4	Hitachi BWR-4	760	1973-02-12	1978-10-12
	Fukushima Daiichi	5	Toshiba BWR-4	760	1972-05-22	1978-04-18
	Fukushima Daini	1	Toshiba BWR-5	1067	1976-03-16	1982-04-20
	Fukushima Daini	2	Hitachi BWR-5	1067	1979-05-25	1984-02-03
	Fukushima Daini	3	Toshiba BWR-5	1067	1981-03-23	1985-06-21
	Fukushima Daini	4	Hitachi BWR-5	1067	1981-05-28	1987-08-25
	Hamaoka	1	BWR-4	515	1971-06-10	1976-03-17
Japan	Hamaoka	2	BWR-4	806	1974-06-14	1978-11-29
	Hamaoka	3	BWR-5	1056	1983-04-18	1987-08-28
	Hamaoka	4	BWR-5	1092	1989-10-13	1993-09-03
	Hamaoka	5	ABWR	1325	2000-07-12	2005-01-18
	Higashidōri (Tōhoku)	1	BWR-5	1067	2000-11-07	2005-12-08
	Higashidōri (Tokyo)	1	ABWR	1350	2011-01-25	
	Kashiwazaki-Kariwa	1	BWR-5	1067	1980-06-05	1985-09-18
	Kashiwazaki-Kariwa	2	BWR-5	1067	1985-11-18	1990-09-28
	Kashiwazaki-Kariwa	3	BWR-5	1067	1989-03-07	1993-08-11

Table 21-2: Non-GE Boiling Water Reactors Worldwide

Country	Plant Name	Unit No.	Model	Capacity (MW)	Begin Building	Commercial Operation
	Kashiwazaki-Kariwa	4	BWR-5	1067	1990-03-05	1994-08-11
	Kashiwazaki-Kariwa	5	BWR-5	1067	1985-06-20	1990-04-10
	Ōma	1	ABWR	1325	2010-05-07	
	Onagawa	1	BWR-4	498	1980-07-08	1984-06-01
	Onagawa	2	BWR-5	796	1991-04-12	1995-07-28
	Onagawa	3	BWR-5	796	1998-01-23	2002-01-30
	Shika	1	BWR-5	505	1989-07-01	1993-07-30
	Shika	2	ABWR	1108	2001-08-20	2006-03-15
	Shimane	1	BWR-3	439	1970-07-02	1974-03-29
	Shimane	2	BWR-5	789	1985-02-02	1989-02-10
	Shimane	3	ABWR	1325	2007-10-12	
Spain	Santa María de Garoña	1	BWR-3	446	1971-05-11	1975-02-15
	Marviken	1	R4	196	1965-04-01	
	Barsebäck	1	ASEA-II	600	1971-02-01	1975-07-01
	Barsebäck	2	ASEA-II	600	1973-01-01	1977-07-01
	Forsmark	1	ASEA-III, BWR-2500	986	1973-06-01	1980-12-10
Sweden	Forsmark	2	ASEA-III, BWR-2500	1116	1975-01-01	1981-07-07
Sweden	Forsmark	3	ASEA-IV, BWR-3000	1167	1979-01-01	1985-08-18
	Oskarshamn	1	ASEA-I	473	1966-08-01	1972-02-06
	Oskarshamn	2	ASEA-II	638	1969-09-01	1975-01-01
	Oskarshamn	3	ASEA-IV, BWR-3000	1450	1980-05-01	1985-08-15
	Ringhals	1	ASEA-I	881	1969-02-01	1976-01-01
	Elk River	1	ACF BWR	22	1959-01-01	1964-07-01
USA	La Crosse	1	Allis-Chalmers BWR	48	1963-03-01	1969-11-07
	Pathfinder	1	Allis-Chalmers BWR	59	1959-01-01	1966-08-01